

# Boundary and Annexation Survey (BAS) Respondent Guide: GUPS

Instructions for Using the Geographic Update Partnership Software (GUPS)

Revised as of February 26, 2018







### **Table of Contents**

Tabl	e of Contents	iii
LIST	OF TABLES	V
LIST	OF FIGURES	vii
Introd	luction	viii
A.	The Boundary and Annexation Survey	viii
B.	What's New for the BAS?	viii
C.	Key Dates for BAS Respondents	viii
D.	BAS State Agreements	ix
E.	Legal Disputes	ix
F.	Respondent Guide Organization	ix
Part 1	L: BAS OVERVIEW	1
Secti	ion 1: Process and Workflow	1
1.1	Receiving the GUPS Application and Shapefiles	1
1.2	Getting Help	2
1.	2.1 GUPS Help	2
1.3	BAS Help	2
Secti	ion 2: Reviewing BAS Data	3
2.1	Boundary Corrections	3
2.2	Legal Boundary Changes	3
2.3	Reviewing Legal Boundaries	3
	5	4
		6
	thic Areas	6
3.1	Validating Updates	11
3.2	Submitting Files Through SWIM	
3.3	Submitting Files on DVD	12
Part 2	2: How To Use GUPS	13
Secti	ion 4: Requirements and installation	13
4.1	Getting Started	14
4.1	How to Install GUPS	15
Secti	ion 5: Using GUPS (Basics and Map Management)	19
5.1	How to Access BAS Shapefiles	
5.2	How to Start a New Project Using GUPS to Import Data from the Census Bureau's BAS	
Web	site (Recommended Method)	20
5.3	Download Shapefiles from the BAS Web site to Your Hard Drive	32
5.4	Download Shapefiles from the Census Bureau ftp2 Site	34
5.5	Use GUPS Interface	37
5.	5.1 GUPS Main Page	
	5.2 Table of Contents and Map View	
	5.3 Managing the Map View from Within the Table of Contents	
5.6	Menu & Toolbars	
5.7	How to Import User-Provided Data into GUPS	
5.	7.1 The Add Data Toolbar	65

	5.7.2	How	to Upload User-Provided Data Layers	66
	5.7.3	How	to Import a Shared ZIP Shapefile	68
S	ection	6: N	aking BAS Updates in GUPS	71
	6.1 H	ow to	Update Legal Boundaries	71
	6.1.1	Rec	ording an Annexation	71
	6.1.2	Rec	ording a Deannexation	78
	6.1.3	Addi	ng a New Legal Entity (New Incorporation)	83
	6.1.4	Dele	ting an Entity (Disincorporation)	92
	6.1.5	Mak	ing a Boundary Update on a County Line	95
	6.1.6	Mak	ing a Legal Boundary Change for a Consolidated City	103
	6.1.7	Mak	ing a Boundary Correction (Add Area/Remove Area)	103
	6.1.8	Addi	ng a Geographic Corridor	106
	6.1.9	Add	a Geographic Offset	114
	6.2 H	ow to	Update Linear Features	115
	6.3 H	ow to	Update Area Landmarks and Hydrographic Areas	121
	6.3.1	Addi	ng a New Area Landmark/Hydrographic Area	121
	6.3.2	Dele	ting an Area Landmark/Hydrographic Area	125
	6.3.3		ng Area to an Area Landmark or Hydrographic Area	
	6.3.4		oving Area from an Area Landmark/Hydrographic Area	
			Update Point Landmarks	
			Use GUPS Review and Validation Tools	
		•	a Printable Map	
			Export ZIP Files to Share/Submit	
S	ection	<b>7:</b> S	ubmitting Your Files to the Census Bureau Through SWIM	160
Α	ppendic	es		166
	 Appendi	х A.	BAS Contact Information and Resources	A-1
	Appendi	хB.	Terms	B-1
	Appendi	x C.	MTFCC Descriptions	C-1
	Appendi	хD.	Standard Street Type Abbreviations	D-1
	Appendi	хE.	GUPS Tools	E-1
	E.1 Se	et Lay	er Symbology	
	E.2 CI	hange	Label Display	E-3
	E.3 R	estorir	ng Default Label Display Settings	E-6
	E.4 Us	sing th	e Table of Contents Toolbar to Manage Layers	E-7
	E.5 Pr	reset \	/iews in the Manage Layer Visibility Table of Contents	
	Appendi	x F.	MAF/TIGER Feature Classification	F-1
	Appendi	x G.	Shapefile Names	G-1
	Annendi	vμ	Shanefile Lavouts	⊔ 1

#### **LIST OF TABLES**

Table 1: Available Change Types by Entity Type	3
Table 2: Acceptable MTFCCs for New Area Landmarks / Hydrographic Areas	6
Table 3: Restricted Point Landmark MTFCCs	7
Table 4: GUPS Hardware and Software Requirements	12
Table 5: Install the GUPS Application	13
Table 6: Start a New Project Using Shapefiles from the BAS Web site	18
Table 7: Download Shapefiles from the BAS Web site to a Hard Drive	
Table 8: Download Shapefiles from ftp2 Site to a Hard Drive (State Users)	32
Table 9: GUPS Main Page Elements	35
Table 10: Menu Tabs and Their Functions	40
Table 11: Adjust Snapping Tolerances	44
Table 12: Standard Toolbar Buttons	
Table 13: Identify a Feature on the Map	47
Table 14: Select/Deselect Features on the Map	49
Table 15: Select Features by Querying the Attribute Table	52
Table 16: View Layer Attributes Using the Attributes Table	54
Table 17: Measure Distances, Area, and Angles on a Map	
Table 18: Bookmark Locations on a Map	
Table 19: BAS Toolbar Buttons	
Table 20: Status Bar Elements	
Table 21: Add Data Toolbar Buttons	
Table 22: Load Shapefiles/Geodatabase Layers	
Table 23: Load Data from a Web Mapping Service	
Table 24: Add Imagery Files	
Table 25: Import a ZIP File Shared by Another User	
Table 26: Record an Annexation	
Table 27: Recording a Deannexation	
Table 28: Adding a New Legal Entity	
Table 29: Record a Disincorporation	
Table 30: Record an Annexation in an Adjacent County	
Table 31: Making a Boundary Correction	
Table 32: Adding a Geographic Corridor	
Table 33: Adding a Linear Feature	
Table 34: Deleting a Linear Feature	
Table 35: Restoring a Deleted Linear Feature	
Table 36: Changing the Attributes of a Linear Feature	
Table 37: Creating a New Area Landmark/Hydrographic Area	
Table 38: Deleting an Area Landmark/Hydrographic Area	
Table 39: Adding Area to an Area Landmark/Hydrographic Area	
Table 40: Removing Area from an Area Landmark/Hydrographic Area	
Table 41: Adding a Point Landmark	
Table 42: Deleting a Point Landmark	
Table 43: Changing the Attributes of a Point Landmark	
Table 44: Using the Geography Review Tool	
Table 45: Reviewing Change Polygons	
Table 46: Export a Printable Map.	
Table 47: Exporting Files to Share with Another User	141

Table 48: Exporting Files for Submission to the Census Bureau	143
Table 49: Transmitting Files to the Census Bureau Using SWIM	146
Table 50: Reset Layer Symbology	E-1
Table 51: Change Default Labeling	E-3
Table 52: Restoring Default Labeling	E-5
Table 53: Table of Contents Layers Toolbar Buttons	E-6
Table 54: MAF/TIGER Feature Classification	F-1
Table 55: State Shapefiles Names	G-1
Table 56: County Shapefiles Names	G-2
Table 57: Edges Shapefile (PVS_18_v2_edges)	H-1
Table 58: Address Ranges Attribute File (PVS_18_v2_addr)	H-2
Table 59: Census Block Shapefile (PVS_18_v2_tabblock2010)	H-3
Table 60: Census Tract Shapefile (PVS_18_v2_curtracts)	H-4
Table 61: American Indian Areas Shapefile (PVS_18_v2_aial)	
Table 62: County and Equivalent Areas Shapefile (PVS_18_v2_county)	H-6
Table 63: County Subdivisions Shapefile (PVS_18_v2_mcd)	H-7
Table 64: Incorporated Place Shapefile (PVS_18_v2_place)	H-8

#### **LIST OF FIGURES**

Figure 1. BAS Workflow	1
Figure 2. GUPS Main Page Layout	35
Figure 3. Close Table of Contents	37
Figure 4. Restore the Table of Contents	38
Figure 5. Managing Layer Visibility	38
Figure 6. Menu and Toolbars	39
Figure 7. Manage Layer Toolbar	39
Figure 8. Standard Toolbar	45
Figure 9. Sub-tool Markers	45
Figure 10. BAS Toolbar	58
Figure 11. Status Bar	59
Figure 12. Add Data Toolbar	60
Figure 13. Annexed Area Corridor and Unincorporated Area	B-2
Figure 14. Incorporated Area and Unincorporated Area	B-2
Figure 15. Participant Responses	B-2
Figure 16. A Cadastral (Parcel-Based) Boundary Map	B-3
Figure 17. How a Boundary Should be Represented When Sent to the Census Bureau	B-3
Figure 18. Place Boundary – Front Lot Line	B-4
Figure 19. Place Boundary – Rear Lot Line	B-4
Figure 20. Table of Contents Layers Toolbar	E-6
Figure 21. Add Preset Layer	E-7
Figure 22. Visibility Presets Dialog Box	E-7

#### INTRODUCTION

#### A. The Boundary and Annexation Survey

The U.S. Census Bureau (Census Bureau) conducts an annual survey called the Boundary and Annexation Survey (BAS) to collect information about selected legally defined geographic areas, such as counties (and equivalent areas), incorporated places, minor civil divisions (MCDs), federally recognized American Indian Areas (AIAs), including reservations, off-reservation trust lands and tribal subdivisions, Hawaiian Homelands, and Alaska Native Regional Corporations (ANRC). The BAS also provides an opportunity for participants to review the names and geographic relationships for these areas. Title 13, U.S.C., Section 6, authorizes this survey.

The Census Bureau uses the boundary information collected during the BAS to tabulate data for the decennial and economic censuses, and to support the Population Estimates Program (PEP) and the American Community Survey (ACS). Maintaining correct boundaries and boundary-to-feature relationships through the BAS helps ensure that the Census Bureau assigns the appropriate population to each governmental unit (GU).

In compliance with the Office of Management and Budget Circular A-16, the BAS supports the Census Bureau's spatial data steward responsibilities for the Federal Geographic Data Committee (FGDC) and the Geospatial One-Stop by updating the inventory and boundaries of GUs.

In addition, the BAS is the source of up-to-date information on changes to the boundaries, codes and names of incorporated places, MCDs, counties (and equivalent areas), Hawaiian Homelands, ANRC, and federally recognized AIAs, which include reservations and off-reservation trust lands used by the U.S. Geological Survey's (USGS), the National Map, and the Geographic Names Information System (GNIS).

Please visit the BAS program Web site at <a href="https://www.census.gov/programs-surveys/bas.html">https://www.census.gov/programs-surveys/bas.html</a>.

For more information on the BAS, please view the "Introduction to BAS" video series on the Census Bureau's BAS Web site at

<a href="https://www.census.gov/programs-surveys/bas/library/videos/bas-intro.html">https://www.census.gov/programs-surveys/bas/library/videos/bas-intro.html</a>

#### B. What's New for the BAS?

1. The Geographic Partnership Support Desk (GPSD) is now fully functional and available to assist with any questions respondents may have regarding BAS.

2. Redistricting data contacts participating in the Voting District Project (VTDP) may submit boundary updates for reconciliation with BAS contacts.

#### C. Key Dates for BAS Respondents

**January 1**—All boundary changes must be legally in effect on or before this date to be reported in the current survey year.

**March 1**—BAS submission date deadline for boundary updates to be reflected in the ACS and PEP published data. Boundary submissions received by this date are also reflected in next year's BAS materials.

**May 31**—BAS boundary updates submitted by this date will be reflected in next year's BAS materials.

#### D. BAS State Agreements

The Census Bureau has established a number of agreements with states for reporting boundary changes. Please visit the BAS State Agreements webpage within the BAS program Web site at <a href="https://www.census.gov/programs-surveys/bas/information/state-agreements.html">https://www.census.gov/programs-surveys/bas/information/state-agreements.html</a> or call (800) 972-5651 for information regarding state agreements.

**Note:** The Census Bureau can only establish BAS state agreements for states that require local governments to report boundary changes to a state agency.

#### E. Legal Disputes

If the Census Bureau discovers that an area of land is in dispute between two or more jurisdictions, the Census Bureau will not make any boundary corrections until the parties come to a written agreement, or there is a documented final court decision regarding the dispute.

If you have questions concerning this, please contact the Census Bureau Legal Office at

#### 301-763-9844.

For disputes involving tribal areas, the Census Bureau must defer to the Office of the Solicitor at the Department of the Interior for a legal opinion. Often complicated land issues require an extended period of time for resolution, and in those cases, the Census Bureau will retain the current boundary in the database until a legal opinion is issued by the Solicitor's office.

#### F. Respondent Guide Organization

This guide has been created for those who choose to participate in the survey using GUPS. Those using their own GIS should consult the *Boundary and Annexation Survey Respondent Guide: Digital* available on the BAS Web site:

<a href="https://www.census.gov/programs-surveys/bas/information/response-methods.Digital\_BAS.html">https://www.census.gov/programs-surveys/bas/information/response-methods.Digital\_BAS.html</a>. Those using paper maps should consult the *Boundary and Annexation Survey Respondent Guide: Paper*. This guide is equipped with shortcuts to subjects that respondents may want to jump to directly. To move directly to one of these sections, click on the linked text.

This guide contains two parts:

#### Part 1: Provides an overview of BAS. It specifies the:

- BAS Process and Workflow;
- Receiving the GUPS Application and Shapefiles;
- GUPS Help;
- BAS Help;
- Reviewing BAS Data (Information specific to the review and update of each type of geographic entity);
- Boundary Corrections (Including Legal Boundary Changes and Reviewing Legal Boundaries);
- Reviewing Linear Features (Including Reviewing Area Landmarks and Hydrographic Areas);
- Reviewing Point Landmarks;
- Validating Updates; and
- Submitting Files Through SWIM and Submitting Files on DVD.

## Part 2: Describes GUPS and gives step-by-step instructions (Action/Result in table format) for how to:

- How To Use GUPS application;
- Requirements and installation;
- How to Access BAS Shapefiles; Download Shapefiles from the BAS Web site to Your Hard Drive; and Download Shapefiles from the Census Bureau ftp2 Site;
- How to Import User-Provided Data into GUPS;
- How to Import a Shared ZIP Shapefile;
- · How to Update Legal Boundaries;
- How to Update Linear Features;
- · How to Use GUPS Review and Validation Tools;
- Export a Printable Map; and
- How to Export ZIP Files to Share/Submit.

<b>Note:</b> In all the Action/Result tables, the action is ususally a command or action you need to p the Result(s) of the action will be shown in italics. For example: if you click GUPS icon c desktop, the software should begin to run automatically.		

#### **PART 1: BAS OVERVIEW**

#### **SECTION 1: PROCESS AND WORKFLOW**

**Figure 1** below illustrates the three phases of the work to be completed for the BAS. The first section in the diagram includes initial steps. The second section indicates the types of geographic data that should be reviewed and updated. The final section lists the final steps to validate and submit changes.




Figure 1. BAS Workflow

Sections 1, 2, and 3 of this guide are organized around the topical areas in the diagram and provide needed program information and procedures, as well as relevant deadlines.

See Appendix A.: BAS Contact Information and Resources for a list of contacts and helpful program links.

#### 1.1 Receiving the GUPS Application and Shapefiles

GUPS is available for installation two ways. GUPS software is available for download directly from the BAS Web site

<a href="https://www.census.gov/programs-surveys/bas/technical-documentation/gups-instructions.html">https://www.census.gov/programs-surveys/bas/technical-documentation/gups-instructions.html</a>. You can also request to receive GUPS software on DVD, which will be shipped to you in a package containing the GUPS DVD, respondent guide, and a read me text file.

Once you have installed GUPS on your computer, the BAS shapefiles can be imported from the BAS Web site directly to the GUPS application. Instructions on how to load data into GUPS appears in **Section 5.2**. If you do not have Internet access, you may request shapefiles on DVD. To request a data DVD, call 1-800-796-3748 or email <a href="mailto:geo.bas@census.gov">geo.bas@census.gov</a>.

#### 1.2 Getting Help

#### 1.2.1 GUPS Help

Part 2: How To Use GUPS of this guide contains directions for how to use the tools available within the GUPS application, as well as step-by-step instructions for how to carry out specific shapefile updates (e.g., annexations and deannexations, adding and deleting features and landmarks, etc.).

Embedded within the GUPS application (under the **Help** tab menu) are other resources, including a short training video on how to submit a ZIP file through SWIM. Additional videos will be provided on the BAS Web site as they become available. In addition, a Section 508-compliant version of this guide is available there. The **Help** menu provides a link to both.

For supplemental information on functions within the GUPS that are specific to QGIS, a QGIS user's manual can be found at

<a href="http://docs.qgis.org/2.8/en/docs/user\_manual/index.html">http://docs.qgis.org/2.8/en/docs/user\_manual/index.html</a>. The QGIS manual offers particularly helpful information on several activities that are touched on in this guide, but not described in detail, including working with user-provided data layers, creating search expressions for attribute tables, and creating customized coordinate systems. For questions concerning technical problems with the GUPS application, user support is available via telephone (1-800-972-5651) and email <a href="mailto:geo.bas@census.gov">geo.bas@census.gov</a>.

#### 1.3 BAS Help

BAS participants may find the *Boundary and Annexation Survey Respondent Guide: Digital* helpful. Although designed for experienced GIS users, it provides important information on geocoding, topological relationships, and spatial accuracy relevant to Census shapefiles. This guide can be downloaded at:

<a href="https://www.census.gov/programs-surveys/bas.html">https://www.census.gov/programs-surveys/bas.html</a>.

The Census Bureau has also created a number of other BAS-related videos, including a helpful one on the subject of topology and why topology is important to the BAS. To view these videos, go to: <a href="https://www.census.gov/programs-surveys/bas/library/videos.html">https://www.census.gov/programs-surveys/bas/library/videos.html</a>>.

#### SECTION 2: REVIEWING BAS DATA

The Census Bureau requests that you review and update all legal entities and boundaries within your jurisdiction, including the new incorporation or disincorporation of legal entities, legal boundary changes, and boundary corrections. You may also update linear features and landmarks, including area landmarks, hydrographic areas, and point landmarks, although review of these is optional.

To help conduct your review, the GUPS application will allow you to import and overlay your own geospatial data layers with the Census Bureau shapefiles. You can import image files from web mapping services, geodatabases, and also other file types. Steps to import the most common types of user-provided data are provided in **Section 5.7 How to Import User-Provided Data into GUPS.** 

#### 2.1 Boundary Corrections

A boundary correction is the adjustment of a boundary to correct an error in how the Census Bureau depicts an existing boundary. Boundary corrections should follow the general shape of the existing boundary. Legal documentation is not required when submitting a boundary correction to the Census Bureau.

#### 2.2 Legal Boundary Changes

Legal boundary changes are the result of legal actions (e.g., annexations), and documenting such changes is the primary goal of the BAS. AIA Legal documentation (e.g., statute, federal court decision, trust deed) must accompany all AIA legal boundary changes, while legal boundary change submissions from incorporated places, MCDs, and counties must provide an authorization number, such as a resolution or ordinance number.

#### 2.3 Reviewing Legal Boundaries

When reviewing legal boundaries, please examine the Census Bureau shapefiles for all legal entities in your jurisdiction. These includes:

- Incorporated places;
- Minor Civil Divisions (MCDs) such as towns, boroughs, and townships;
- · Counties (and county equivalents); and
- Consolidated cities.

The **Table 1** shows the specific changes allowed for each legal entity type.

Table 1: Available Change Types by Entity Type

Entity Type	Available Change Types	
Incorporated Place	<ul> <li>New Entity (New incorporation)</li> <li>Deleted Entity (Disincorporation)</li> <li>Addition or Annexation</li> <li>Deletion or Deannexation</li> <li>Boundary Correction (add)</li> <li>Boundary Correction (remove)</li> <li>Geographic Corridor</li> <li>Geographic Offset</li> </ul>	
Minor Civil Division (MCD)	<ul> <li>New Entity</li> <li>Deleted Entity</li> <li>Addition or Annexation</li> <li>Deletion or Deannexation</li> <li>Boundary Correction (add)</li> <li>Boundary Correction (remove)</li> <li>Geographic Corridor</li> <li>Geographic Offset</li> </ul>	
County	<ul> <li>New Entity (New incorporation of place and MCD)</li> <li>Deleted Entity (Disincorporation of place and MCD)</li> <li>Addition or Annexation</li> <li>Deletion or Deannexation</li> <li>Boundary Correction (add)</li> <li>Boundary Correction (remove)</li> <li>Geographic Corridor</li> <li>Geographic Offset</li> </ul>	
Consolidated City	<ul> <li>New Entity (New incorporation of place and MCD)</li> <li>Deleted Entity (Disincorporation of place and MCD)</li> <li>Addition or Annexation</li> <li>Deletion or Deannexation</li> <li>Boundary Correction (add)</li> <li>Boundary Correction (remove)</li> <li>Geographic Corridor</li> <li>Geographic Offset</li> </ul>	

#### 2.4 Requirements for Legal Boundary Changes

#### 2.4.1 Boundary Changes to Legal Entities

For a boundary change to an existing legal entity (or the new incorporation or disincorporation of a legal entity) to be processed as a legal change, you must provide the legal documentation number (e.g., law or ordinance number), effective date, and authorization type. You are not required to submit paperwork documenting the change.

**Note:** Although additional documentation is not required, we do strongly encourage you to attach supporting paperwork to your submission (you may do this directly in GUPS). The paperwork will expedite our ability to reconcile and process any legal updates.

#### 2.4.2 Boundary Changes to Legal Entities in Georgia and Indiana

**Georgia**: Any legal boundary change made to an incorporated place in the state of Georgia must include: (1) the effective date, and (2) the acreage of the new entity. In

addition, before entering the change, you must ensure that all annexation/deannexation information has been reported to the Department of Community Affairs (DCA). The DCA provides the Census Bureau a list of the entities that reported boundary changes each year. Any legal boundary changes to incorporated places not on this list will not be placed in the MAF/TIGER System. For additional information, see: <a href="https://www.census.gov/programs-surveys/bas/technical-documentation/methodology/state-agreements.html">https://www.census.gov/programs-surveys/bas/technical-documentation/methodology/state-agreements.html</a>.

**Indiana**: Per Indiana state law, counties must provide the legal boundary updates for townships. For more information, refer to Indiana Code 36-6 Government of Townships at <a href="http://iga.in.gov/legislative/laws/2017/ic/titles/001">http://iga.in.gov/legislative/laws/2017/ic/titles/001</a>. If you have questions about required documentation for your particular jurisdiction, contact the Geography Division by phone at

1-800-972-5651 or by email at <a href="mailto:geo.bas@census.gov">geo.bas@census.gov</a>.

#### 2.5 Reviewing Linear Features

It is important that Census Bureau data reflects the most recent linear features to ensure that new or previously missed housing units located along these features are identified and located. When reviewing linear features (edges layer) on the Census Bureau shapefiles, first determine whether any features are missing or need to be deleted. Pay particular attention to areas that have experienced recent population growth or construction activities, as these are the most likely to possess new or altered linear features (e.g., new subdivisions, traffic circles converted to straight ways, or privately maintained roads that serve as public streets, but exclude private driveways).

You may also add attribute updates (e.g., name, class code, and address ranges) for selected features. For a complete list of MAF/TIGER Feature Class Codes (MTFCCs), review

#### **Appendix C. MTFCC Descriptions.**

To aid in the review of linear features, GUPS allows you to import local street centerline files, hydrography layers, imagery, and other user-provided geospatial data for reference and comparison against the Census Bureau data.

#### In your review, please note:

- **S1100** and **S1200**—If you add road features with an MTFCC of S1100 (Primary Road) or S1200 (Secondary Road), you must supply a feature name. As is the case for all road features, the feature name should be a proper name or route number.
- Spatial Inaccuracies—The Census Bureau will not process the wholesale spatial realignment of features to enhance spatial accuracy. If a feature is in the incorrect location, delete the feature and add it in the correct location. Take this action only if the feature is exceedingly spatially inaccurate and/or the current location (with respect to other features and boundaries) affects the tabulation of housing units to the correct geography, such as legal entities, census tracts, and census blocks.
- Address Range Changes—The Census Bureau accepts address range data as part of the linear
  feature update layer. As with other linear feature updates, you must supply the required attributes
  and corresponding change type for the update. In addition, because existing address ranges are
  not shown in our outgoing shapefiles, we recommend that participants only add address ranges
  to new features.

#### 2.6 Reviewing Area Landmarks and Hydrographic Areas

The Census Bureau accepts updates to area landmarks and hydrographic areas in a similar manner to legal boundary changes. However, area landmarks and hydro areas are not legal entities, so no documentation or effective dates are required.

Allowable updates for area landmarks and hydrographic areas are:

- Add new area landmark or hydrographic area;
- Remove area landmark or hydrographic area;

- Change or add landmark name; and
- Boundary corrections (add and remove area).

If you *add* a new area landmark or hydrographic area, please add only:

- Water bodies;
- Glaciers;
- Airports;
- Cemeteries;
- · Golf courses; and
- Parks.

The Census Bureau cannot add other types of area landmark / hydrographic areas to the MAF/TIGER System at this time (even though others may already exist in the database).

Table 2 shows the acceptable MTFCCs for new area landmarks or hydrographic areas.

Table 2: Acceptable MTFCCs for New Area Landmarks / Hydrographic Areas

MTFCC	Description
H2030	Lake/Pond
H2040	Reservoir
H2041	Treatment Pond
H2051	Bay/Estuary/Gulf/Sound
H2081	Glacier
C3023	Island
K1231	Hospital/Hospice/Urgent Care Facility
K1235	Juvenile Institution
K1236	Local Jail or Detention Center
K1237	Federal Penitentiary, State Prison, or Prison Farm
K2110	Military Installation
K2180	Park
K2181	National Park Service Land
K2182	National Forest or Other Federal Land
K2183	Tribal Park, Forest, or Recreation Area
K2184	State Park, Forest, or Recreation Area
K2185	Regional Park, Forest, or Recreation Area
K2186	County Park, Forest, or Recreation Area
K2187	County Subdivision Park, Forest, or Recreation Area
K2188	Incorporated Place Park, Forest, or Recreation Area
K2189	Private Park, Forest, or Recreation Area
K2190	Other Park, Forest, or Recreation Area (quasi-public, independent park, commission, etc.)
K2424	Marina
K2540	University or College

MTFCC	Description
K2457	Airport - Area Representation
K2561	Golf Course
K2582	Cemetery

**Note:** If adding an MTFCC K2457 (Airport – Area Representation) area landmark, please limit the updates to major airports (major regional and international airports). The feature should show the full extent of the airport facility, that is, do not limit the addition to simply the landing strips.

#### Area Landmark / Hydro Area Changes May Be Delayed

The Census Bureau prioritizes boundary changes to legal areas to meet ACS, PEP, and BAS deadlines. Therefore, there may be delays in incorporating area landmark and hydrographic area changes to the MAF/TIGER System. Please do not resubmit any changes that were sent during the previous year's BAS. We are working on incorporating those changes, and they will be reflected in the next year's BAS materials.

#### 2.7 Reviewing Point Landmarks

Because many of the point landmarks contained in the Census Bureau's MAF/TIGER System originate from the U.S. Geological Survey's Geographic Names Information System (GNIS), which is the official gazetteer of point landmark names for the Federal Government, point landmark updates are limited in the BAS. The Census Bureau cannot modify any point landmark imported from the GNIS database. Thus, be aware that name changes or deletions submitted for the following types of landmarks may be left unchanged:

- K2451 (Airport or Airfield);
- K2582 (Cemetery);
- C3022 (Summit or Pillar); and
- C3081 (Locale or Populated Place).

Also, due to Title 13 privacy concerns, any landmark with an MTFCC shown in **Table 3** below cannot be added to the MAF/TIGER System as a point landmark. The MAF/TIGER System no longer maintains any point landmarks with these MTFCCs. Landmarks with these codes could identify a residence or private business. Thus, it is also important *not* to add any of the point landmark types shown in the table using alternative MTFCCs.

**Table 3: Restricted Point Landmark MTFCCs** 

MTFCC	Description
K1100	Housing Unit Location
K1121	Apartment Building or Complex
K1122	Rooming or Boarding House

MTFCC	Description	
K1223	Trailer Court or Mobile Home Park	
K1226	Housing Facility/Dormitory for Workers	
K1227	Hotel, Motel, Resort, Spa, Hostel, YMCA, or YWCA	
K1228	Campground	
K1229	Shelter or Mission	
K1232	Halfway House/Group Home	
K1233	Nursing Home, Retirement Home, or Home for the Aged	
K1234	County Home or Poor Farm	
K1235	Juvenile Institution	
K1241	Sorority, Fraternity, or College Dormitory	
K1251	Military Group Quarters	
K1299	Other Group Quarters Location	
K2100	Governmental	
K2197	Mixed Use/Other Non-residential	
K2300	Commercial Workplace	
K2361	Shopping Center or Major Retail Center	
K2362	Industrial Building or Industrial Park	
K2363	Office Building or Office Park	
K2364	Farm/Vineyard/Winery/Orchard	
K2366	Other Employment Center	
K2424	Marina	
K2500	Other Workplace	
K2564	Amusement Center	

#### **SECTION 3:**

#### Point Landmark Changes May Be Delayed

The Census Bureau prioritizes boundary changes to legal areas to meet ACS, PEP, and BAS deadlines. Therefore, there may be delays in incorporating point landmark changes to the MAF/TIGER System. Please do not resubmit any changes that were sent during the previous year's BAS. We are working on incorporating those changes, and they will be reflected in the next year's BAS materials.

#### QUALITY CONTROL AND FILE SUBMISSION

#### 3.1 Validating Updates

Once you have completed your BAS updates, you must complete a review of your change polygons to ensure that:

- **1.** The polygons have no unintended holes (e.g., you annexed several faces but missed a traffic circle or small pond).
- **2.** All boundary corrections meet a minimum size threshold (very small corrections cannot be processed).

#### Validate Often

Validation tools in GUPS can be accessed at any time while you are working in the application. We suggest you utilize them as you work to identify errors early and avoid extensive rework. Steps to use the Geographic Review tool and the Review Change Polygons tool are included in **Section 6.5 How to Use GUPS Review and Validation Tools**.

#### 3.2 Submitting Files Through SWIM

Prompt submission of updates is appreciated. It benefits the Census Bureau—allowing us to review the files early, provide feedback, and avoid backups in file processing—and you—guaranteeing your updates are recorded accurately and are reflected in the latest releases of Census Bureau data products.

For those with Internet access, all BAS submissions must be made via the Secure Web Incoming Module (SWIM). Due to security reasons, we cannot accept files sent via email or through our alternate ftp sites.

If you indicated on your "Annual Response Form" that you wished to receive the GUPS application, you will automatically receive the SWIM URL and a registration token via email. The email should arrive 5 days after the Annual Response is completed online (or 5 business days after the Census Bureau receives the paper form).

The registration token allows you to establish a personal SWIM account. If you do not receive a SWIM token after the amount of time specified, email <a href="mailto:geo.bas@census.gov">geo.bas@census.gov</a> or call 1-800-972-5651.

Once registered, you will no longer need the token to log into the system.

#### Current SWIM Users

If you are a participant in another Census Bureau partnership program, or participated in a previous BAS year, and already have a SWIM account, you may use your current account to submit files for the BAS. You do not need to set up a new account.

For step-by-step instructions to submit files through the SWIM, refer to **Table 49**. For those without Internet access, see **Section 3.3** below.

#### 3.3 Submitting Files on DVD

If you do not have Internet access, you may copy your ZIP file(s) to DVD for submission. The DVD should be mailed to:

U.S. Census Bureau National Processing Center ATTN: BAS Returns, Bldg 63E 1201 East 10th Street Jeffersonville, IN 47132

#### **PART 2: HOW TO USE GUPS**

#### **SECTION 4: REQUIREMENTS AND INSTALLATION**

This section includes information needed to use GUPS. It offers a description of the GUPS application and gives specific instructions (in the form of Step / Action tables) for how to use GUPS to make BAS updates. Reminder: this guide is equipped with shortcuts to subjects that respondents may want to jump to directly. To move directly to one of these sections, click on the linked text.

#### Part 1: Requirements and installation

- Getting Started Lists the hardware and software requirements for GUPS and SWIM; and
- How to Install GUPS Provides instructions for installing the application.

#### Part 2: Using GUPS (Basics and Map Management)

 How to Access BAS Shapefiles - Provides instructions to open GUPS, start a project, and load shapefiles;

How to Start a New Project Using GUPS to Import Data from the Census Bureau's BAS Website (Recommended Method);

- Error: Reference source not found;
- Use GUPS Interface Including the Menu, Toolbars, Table of Contents or Map Legend, and the Map View area;
- Menu & Toolbars Offers instructions for using the tools available through the menu and toolbars;
- Error: Reference source not found;
- How to Upload User-Provided Data Layers; and
- How to Import a Shared ZIP Shapefile.

#### Part 2: Making BAS Updates in GUPS

- How to Update Legal Boundaries Gives instructions to make required and optional updates in the application;
- Adding a New Legal Entity (New Incorporation) and Deleting an Entity (Disincorporation);
- · Making a Boundary Update on a County Line;
- Making a Legal Boundary Change for a Consolidated City;
- Making a Boundary Correction (Add Area/Remove Area);
- Adding a Geographic Corridor and How to Add a Geographic Offset;
- How to Update Linear Features;
- Error: Reference source not found;

#### Error: Reference source not found;

- Error: Reference source not found;
- Export a Printable Map;
- How to Export ZIP Files to Share/Submit; and

Submitting Files Through SWIM.

#### 4.1 Getting Started

Download GUPS from the BAS Web site at: <a href="https://www.census.gov/programs-surveys/bas/technical-documentation/gups-instructions.html">https://www.census.gov/programs-surveys/bas/technical-documentation/gups-instructions.html</a>. If you requested and received the GUPS package, it should include a DVD containing the GUPS software, respondent guides, and a readme text file.

Before beginning the installation, check your computer to verify that it has the capabilities need to run GUPS (using **Table 4** below).

GUPS is based on QGIS (formerly known as Quantum GIS), a free and open-source desktop geographic information system application. You can learn more about QGIS at <a href="http://www.qgis.org/en/site/">http://www.qgis.org/en/site/</a>. The GUPS application was developed for use in a desktop PC or a network environment.

**Table 4** lists the hardware and software requirements to install and run GUPS. Also included are the software requirements to: (1) play training videos available within the application and (2) submit files through the SWIM Web site.

**Table 4: GUPS Hardware and Software Requirements** 

Hardware	Operating System	Browser
Disk Space Needed to Run GUPS:  2.0 GB  Disk Space Needed to Store Shapefiles:  Shapefile sizes vary. To view the size of your shapefiles, select a file/ folder, right-click, and choose Properties in the drop-down menu. The Files Properties box opens and displays the file/folder sizes. Select multiple files/ folders in the list to view their properties via the same method.	Windows:  To run GUPS, users need one of the following Windows operating systems:  Windows XP  Windows Vista  Windows 7  Windows 8  Windows 10  Apple Mac OS X:  Mac OS X users must secure a license for Microsoft Windows and use a Windows bridge. The suggested bridge software is Boot Camp, which comes pre-installed on all Mac computers. See instructions for using Boot Camp at:  https://www.apple.com/support/bootcamp/ge tstarted/>.	Minimum Browser Versions to Play Training Videos:  Internet Explorer 9 Google Chrome 3 Mozilla Firefox 3.5 Apple Safari 4  Minimum Browser Versions to Use SWIM: Internet Explorer 8 Google Chrome 3 Mozilla Firefox 3.5 Apple Safari 4.1.3
<ul><li>RAM:</li><li>4 GB recommended minimum</li></ul>	Important Note: Since Boot Camp requires you to restart your computer to set up the bridge, be sure to print the instructions provided at the URL above before you begin.	

Depending on the Windows OS version, the GUPS dialog boxes may have a different appearance than the screenshots contained in the user guide, although the content is the same.


#### 4.1 How to Install GUPS


To install the GUPS application you must have Administrator privileges for your computer. If you already have GUPS downloaded, please make sure you are using the most current version. Compare the version on your computer with the one provided on the Census Bureau's installation DVD to acquire the latest version. To complete the installation, follow the steps in **Table 5: Install the GUPS Application**.


**Note:** If you already have a version of GUPS installed, please check to make sure you are running the latest version. Go to the **GUPS** tab and click the **About GUPS** option in the drop-down menu to find the GUPS version number. If you are not running the latest version, download and follow the setup instructions which will automatically uninstall the old version before it installs the latest GUPS version.


**Table 5: Install the GUPS Application** 

Step	Action and Result	
Step 1	CLICK THE DIRECT DOWNLOAD LINK <https: geo="" gups="" pvs="" www2.census.gov=""></https:> OR PLACE THE INSTALLATION DVD INTO YOUR COMPUTER'S DVD DRIVE. FOR SOME USERS, A WINDOWS PROTECTED YOUR PC POP-UP BOX MAY APPEAR.	
	Windows protected your PC  Windows SmartScreen prevented an unrecognized app from starting. Running this app might put your PC at risk.  More info  Some users may receive a Windows protected your PC message. Click "More Info" and select "Run anyway" at the bottom. Your computer should automatically run the installer.	
	To continue, click 'More info', then select 'Run anyway?'.	
Step 2	Other users may receive a user account control pop-up that asks, "Do you want to run this file?", "Do you want to allow the following program from an unknown publisher to make changes to this computer?", or a similar query. See an example below.	









# SECTION 5: USING GUPS (BASICS AND MAP MANAGEMENT)

After successfully installing GUPS, you are ready to start your BAS updates. There are three ways to retrieve shapefiles when starting a new project:

- From the Census Web site (loads directly into GUPS);
- From DVD (if one was requested); and
- From My Computer (if you downloaded them to your hardrive).

**Table 6** shows the steps to open GUPS and start a new project using the Census Web site. shows the same steps to open GUPS, but starts a new project using the Census provided DVD or My Computer (downloaded Census shapefiles saved to your hard drive).

#### 5.1 How to Access BAS Shapefiles

BAS shapefiles from the BAS Web site can be pulled directly into the application when working in GUPS. Users can load the shapefiles as needed or load multiple county files at once. This is the preferred method for loading the Census Bureau's BAS Shapefiles into GUPS as it ensures that required files are placed in the correct location for the application to access.

Another option for loading files is to download the shapefiles to your hard drive from the BAS Web site (or from the Census Bureau ftp2 site), then import them into GUPS. BAS shapefiles are also available for download from the BAS Web site here:

<a href="https://www.census.gov/geographies/mapping-files/2019/geo/bas/2019-bas-shapefiles.html">https://www.census.gov/geographies/mapping-files/2019/geo/bas/2019-bas-shapefiles.html</a>. Instructions for how to download Census Bureau shapefiles to your hard drive appear in Table 6 and Table 7. Downloading files to your hard drive is not the preferred method when working in GUPS, and should be used only when necessary (e.g., you need additional data layers that GUPS does not automatically load and want to pull them in as user-provided data).

If you have requested to receive the shapefiles on DVD, you can also load the files directly into GUPS from the DVD. Instructions for how to load shapefiles are contained in **Table 6: Start a New Project Using Shapefiles from the BAS Web site**.

Whether the files are pulled from the BAS Web site or from the DVD, the GUPS application unzips them and places them into a pre-established folder created on your computer's home directory during the installation process (C:\GUPSGIS\gupsdata\ BAS2019\shape). It then displays them in the application. GUPS then manages the files for you. You do not need to take any further action.

#### CAUTION!

Regardless of the source of the shapefiles, it is important that you **DO NOT CHANGE** any shapefile or folder name. The files and folders must have the exact names given for the GUPS application to recognize and load them.

# 5.2 How to Start a New Project Using GUPS to Import Data from the Census Bureau's BAS Website (Recommended Method)


To open the GUPS application and begin your BAS updates, follow the steps in **Table 6** below. Before beginning, note that:


- 1. If you wish to practice using GUPS without committing the changes you make, simply exit the system without saving. Before the system closes, it will give you the option to discard the changes.
- 2. If you feel comfortable with the system, but you do not want to make all your changes in one session, simply save your changes, then close the system. When you open GUPS later, it will allow you to reopen the project and continue working.


**Note:** In all the Action/*Result* tables, the action is ususally a command or action you need to perform and the Result(s) of the action will be shown in italics. For example: if you click the QGIS icon on your desktop, the software should begin to run automatically.


Table 6: Start a New Project Using Shapefiles from the BAS Web site


Step	Action and Result
Step 1	Double-click the QGIS icon on your desktop.
	QGIS Desktop 2.8.3
	The QGIS splash screen appears. (Note: QGIS is the open-source platform on which GUPS is built.)
	Starting Python






















#### Step Action and Result To identify which of the entries in the list represents your project, look at its number string. This string comprises your BAS ID. Each BAS ID is 11 digits. The first digit indicates the Entity Type (i.e., the user type) (0 = consolidated city; 1 = incorporated place; 2 = county; 3 = MCD; and 7 = state). The next two digits are the state FIPS code. The following three digits are the FIPS code for the working county (these digits are '000' for incorporated places). The final five digits are the FIPS code for the specific incorporated place, consolidated city, or MCD that created the project (for counties, these digits are '00000' since the county is already identified in the string). The number string, 12800040360.qgs reflects a project created by a Place user (for the City of Lena) in Mississippi, where 1 = incorporated place; 28 = Mississippi FIPS code; 000 = placeholder number for non-county entities (if the user were a county user this number would be the FIPS code for Chickasaw County, or 155); and 40360 = the place FIPS code for Lena. If you do not know the BAS ID information for your particular geography, it is available within the Map Management dialog box. Below is an example for Hanover Township, an MCD in Jefferson County, Indiana. X Map Management Open Recent ☐Import Project ZIP file Boundary and Annexation Survey Sub Program Boundary and Annexation Survey \* Indiana [18] State FIPS code Working County Jefferson [077] ¥ County FIPS code Entity Type \* County MCD FIPS code **Entity Name** Jefferson County [077] Step 26 Once you have identified the correct file to reopen, select it from the list. The map for the project automatically loads and the layers show in the **Table of Contents**. Census Bureau-defined default layers and view settings are loaded each time you start a new project in GUPS. If you change these settings for a project, when you save the project your new settings are also saved. Thus, when you reopen the project, the Table of Contents and Map View display the layers and the map according to the settings you were last using rather than returning to the Census Bureau default settings. To restore the default settings for a layer: Click on the layer in the **Table of Contents**. A drop-down menu opens. In the drop-down menu, select 'GUPS Layer'. A submenu opens.

In the submenu, select 'Load default style' (see illustration below).



When you reopen a project, also note that any previously selected adjacent (or other selected) counties appear in cyan blue and remain checked. Other adjacent counties that have not previously been selected appear in yellow and are also checked, as shown below.



You may load files for additional counties at this point if you wish.



#### **Loading Multiple Files at Once**

The limit to how many county datasets can be loaded at once is 11 (the working county plus 10 other counties). To load shapefiles for additional counties, after the first 10 are loaded:


- Leave the same working county selected in the Working County field.
- Uncheck the already loaded counties in the Map Management dialog box list.


Step	Action and Result
	<ul> <li>Check the checkboxes for the additional counties (up to 10) that you wish to add. Click the         Open button and after the Select Data Folder, Directory or Location box opens, use the         drop-down menu to select the source of the files. Repeat this process as many times as         needed.</li> </ul>


# 5.3 Download Shapefiles from the BAS Web site to Your Hard Drive

Follow the steps in below to download the files from the BAS Web site to your hard drive.

Table 7: Download Shapefiles from the BAS Web site to a Hard Drive









## 5.4 Download Shapefiles from the Census Bureau ftp2 Site

If you are a state level user, or if you would like to download shapefiles for several counties at one time to your hard drive, follow the steps in **Table 8**.

Table 8: Download Shapefiles from ftp2 Site to a Hard Drive (State Users)





Step	Action and Result
	Index of /geo/pvs/
	Name         Size         Date Modified           2i [parent directory]         9/14/16, 10:44:00 AM           01/         9/14/16, 10:46:00 AM           02/         9/14/16, 10:50:00 AM           04/         9/14/16, 10:50:00 AM           05/         9/14/16, 10:50:00 AM           06/         9/14/16, 11:00:00 AM           08/         9/14/16, 11:10:00 AM           09/         9/14/16, 11:11:00 AM           10/         9/14/16, 11:11:00 AM           11/         9/14/16, 11:11:00 AM           11/         9/14/16, 11:11:00 AM           11/         9/14/16, 11:25:00 AM           11/         9/14/16, 11:25:00 AM           15/         9/14/16, 11:25:00 AM           15/         9/14/16, 11:25:00 AM           15/         9/14/16, 11:36:00 AM           15/         9/14/16, 11:36:00 AM           16/         9/14/16, 11:36:00 AM           17/         9/14/16, 11:36:00 AM           19/         9/14/16, 11:46:00 AM           19/         9/14/16, 11:50:00 AM           19/         9/14/16, 11:50:00 AM           19/         9/14/16, 11:50:00 AM           10/         9/14/16, 11:30:00 PM
Step 5	Select the state folder that contains the county(ies) for which you are downloading data. The state folders are represented using two-digital state FIPS codes.
Step 6	There are several sets of shapefiles within each state directory. You will want to download the most recent partnership shapefiles. These shapefiles are contained within a zip file with the prefix partnership_shapefiles_18v2. Each zip file ends with a five-digit state-county FIPS code (e.g., 08051) which represents the county for which you are downloading data. Make sure to choose the filename with "18v2", because the "18v1" files are sometimes also available in the folders.
Step 7	Select the county or counties that you intend to download and copy to your local or network drive. You may copy the files to any location you wish. When you select your geography in GUPS, the application asks you to specify the location ('CD/DVD', 'My Computer', or 'Census Web') of your files. When you select 'My Computer', GUPS asks you to select a directory. Navigate to the location where you saved the files and select those you wish to upload. GUPS unzips and loads the files, then moves them to the pre-established folder on your home directory.
i	IF YOU HAVE AN FTP CLIENT SOFTWARE SUCH AS WINSCP OR FILEZILLA (OR OTHER) YOU MAY CONNECT TO <ftp: ftp2.census.gov=""></ftp:> WITHOUT A PASSWORD. ENTER 'ANONYMOUS' AS YOUR USER NAME AND ENTER YOUR EMAIL ADDRESS IN PLACE OF A PASSWORD.

#### 5.5 Use GUPS Interface

## 5.5.1 GUPS Main Page

**Figure 2** shows the layout of the main GUPS page. This page contains all the tools needed for making BAS updates. All work is completed from this page. Shown in the figure are the main page elements. These include the:

- 1. Menu;
- 2. Table of Contents;
- 3. Map View (where the data displays);
- 4. Toolbars (Standard toolbar, BAS toolbar, and Add Layers toolbar); and
- 5. Status Bar (at bottom of page).





Figure 2. GUPS Main Page Layout

The purpose for each element on the main GUPS page is explained in **Section 5.5.1** through **Section 5.7.1** describes in detail the individual components and specific functions of each element.

**Table 9: GUPS Main Page Elements** 

Page Element	General Function
Menu	THE MENU OFFERS BASIC FEATURES SUCH AS <b>SETTINGS</b> AND <b>HELP</b> ; TOOLS TO MANAGE THE MAP VIEW AND IMPORT USER-PROVIDED DATA; IMPORTANT CALCULATION, MEASUREMENT, AND GEOPROCESSING TOOLS; AND TOOLS NEEDED TO MAKE SHAPEFILE UPDATES. NOTE THAT ALMOST ALL OF THE FUNCTIONS AVAILABLE FROM THE <b>MENU</b> ARE ALSO AVAILABLE IN THE APPLICATION'S MORE CONVENIENTLY LOCATED TOOLBARS.  Project Edit View Layer Settings Plugins Vector Raster Database Web Processing Help
Table of	The <b>Table of Contents</b> shows the layers on the map for the county you selected.
Contents	The <b>Table of Contents toolbar</b> allows you to add or remove layers (or groups), manage layer visibility, and filter the legend by map content



Page Element	General Function	
Status Bar	Displays information on the map scale, projection, and coordinates and allows you to adjust the display.	
	© Coordinate: -89.1395,42.8410 Scale 1:27,699 ✔ Rotation: 0.0 ♣ ✔ Render ♠ EPSG:4269 (OTF)	

## 5.5.2 Table of Contents and Map View

When you choose your program and geography in the **Map Management** dialog box, GUPS automatically loads a set of default data layers (and default layer groups) defined by the Census Bureau for the program you selected. As the map opens in **Map View**, the list of the preset layers (already grouped) appears in the **Table of Contents**.

You will use the **Table of Contents** and the small **toolbar** appearing at its top to manage your map view. Note that the **Table of Contents** and the **Map View** windows are interdependent. Selections you make in the **Table of Contents** are immediately reflected on the map display.




Figure 3. Close Table of Contents

You can close the Table of Contents at any time to see more of the map (just click on the small 'x' in the upper right-hand corner). To restore the Table of Contents, click the View tab on the Menu, select 'Panels' in the drop-down menu, click the arrow next to 'Panel' to open the submenu, then click on 'Layers'.




Figure 4. Restore the Table of Contents

The **Table of Contents** will then reopen and display in its default position on the page.

## **5.5.3** Managing the Map View from Within the Table of Contents

Within the **Table of Contents**, you can manage layer visibility (i.e., determine what layers display on the map), reorder data layers, and set new layer symbology.

#### 5.5.3.1 Manage Layer Visibility

To add or remove layers from the map view:

- Click the checkbox next to a layer to add it to the map view.
- Uncheck the checkbox next to a layer to remove it from the view.

**OR**, Right-click the name of the layer and select 'Remove' in the drop-down menu.




Figure 5. Managing Layer Visibility

#### 5.5.3.2 Reorder Data Layers

In the **Table of Contents**, the order in which the layers are listed determines how the layers display on the map. The layers at the top display on top of those below them. To change the display order:

- 1. Left-click on the layer name.
- 2. Hold down the mouse button and drag the layer to the desired position in the list.
- **3.** Release the mouse button to place the layer in its new position. The map display will then reflect the new layer order in the **Table of Contents**.

### 5.5.3.3 Expand/Contract Table of Contents Menus

To expand or contract the menu for a layer or layer group:

• Click on the '+' sign to expand the group. When you click the '+' sign next to the layer name place\_55025, the layer's submenu opens:



#### 5.6 Menu & Toolbars

The main **Menu**, the **Standard toolbar**, and the **BAS toolbar** are located at the top of the GUPS page. These toolbars offer general GIS and system tools and allow you to make your BAS updates.



Figure 6. Menu and Toolbars

The **Manage Layer toolbar**, the vertical toolbar located to the left of the **Table of Contents** (shown here in a horizontal position) allows you to import user-provided data.



Figure 7. Manage Layer Toolbar

**Note:** Although the **Menu** is always located at the top of the page and cannot be moved, you may move the toolbars to the location most convenient for you. For example, if you prefer that the **Add Data** 

**toolbar** appear at the top of the page, you can drag it there. This allows you to expand the area available for the **Table of Contents** and **Map View**.

- As you work with the toolbars, hover your mouse over any toolbar button to see the name of the tool it represents. You can also resize and reposition the toolbars by dragging them.
- The Menu, the Standard toolbar, and the BAS toolbar are described in the section below. The Add Data toolbar is discussed in **Section 5.7**, **How to Import User-Provided Data into GUPS**.


#### 5.6.1 Menu Tabs


**Table 10** below defines each of the tabs on the main **Menu**, provides an image of the drop-down options for each, and describes each tab's function.

**Table 10: Menu Tabs and Their Functions** 

Tab	Drop-down Menu	Function / Description
Project	Project  Save Ctrl+S  Save as Image  Exit QGIS Ctrl+Q	From the <b>Project</b> tab, you may save a project, click on 'Save as Image' to create an image file of the map in <b>Map View</b> , or exit the application.  If you click 'Save as Image', GUPS allows you to select a file type for the image (.png, .jpg, .tif, etc.), name the file, and save it to any location on your computer.
Edit	Edit  Undo Ctrl+Z	From the <b>Edit</b> tab, you may 'Undo' your last action or 'Redo' the action (if you selected 'Undo' and then changed your mind).
	Redo Ctrl+Shift+Z	Note: For 'Undo' to work, the correct layer must be selected in the Table of Contents. For example, if you added a linear feature in the Edges layer, then closed the layer and opened the Area Landmarks layer, 'Undo' will not delete the linear feature. You must reselect the Edges layer to undo the linear feature's addition.
		Note: You may undo multiple actions within a layer (e.g., the addition of several linear features) provided you have not yet saved. Once you save an action, 'Undo' is disabled.

Tab	Drop-down Menu	Function / Description
View	View Layer Settings Vector Raster  Pan Map  Pan Map to Selection  Zoom In Ctrl++  Select  Identify Features Ctrl+Shift+I  Measure  Zoom Full Ctrl+Shift+F  Zoom to Layer  Zoom Last  Zoom Next  Decorations  New Bookmark Ctrl+B  Show Bookmarks  Ctrl+Shift+B  Refresh  Panels  Toolbars  Toggle Full Screen Mode F11	The View tab allows you to complete several actions also available on the Standard toolbar. Included are options for navigating the map, identifying feature attributes, measuring distance, and creating spatial bookmarks to return to the same map view at a later time.  From this location you can also:  • Set what toolbars display.  • Restore the Table of Contents if you earlier closed it (click 'Panels' in the drop-down menu, click the right arrow, click 'Layers' in the Layers down-menu).  • Refresh the map to restore it to the original map extent.
Layer	Add Layer  Add from Layer Definition File  Paste style  Remove Layer/Group Ctrl+D  Set Scale Visibility of Layer(s)  Set CRS of Layer(s) Ctrl+Shift+C  Set Project CRS from Layer  Show All Layers Ctrl+Shift+U  Show Selected Layers	The Layer tab allows you to add and remove layers from the map, open the layer attribute table, set the map projection, or Coordinate Reference System (CRS), and display or hide layers.  Note: Many of these same functions are more conveniently located on the Add Layers toolbar and the small toolbar that sits at the top of the Table of Contents.
Settings	Settings  Custom CRS  Style Manager  Customization  Options  Snapping Options	The <b>Settings</b> tab allows you to customize the CRS and map display options and set snapping tolerances (see instructions below this table).
Vector	Vector  Convex Hull(s)  Buffer(s)  Intersect  Vinion  Symetrical Difference  Clip  Difference  Eliminate Sliver Polygons	The <b>Vector</b> tab provides access to several Geoprocessing Tools, which allow you to create buffers around features, overlay areas so that you can create an intersection, union, or symmetrical difference, merge features, and perform other common geoprocessing actions.
Raster	Raster Web Processin	The <b>Raster</b> tab provides access to a Calculator, which allows you to perform calculations on the basis of existing raster






#### Note on Snapping Tolerances

Snapping tolerances in GUPS are pre-defined by layer (e.g., the default tolerance for edges is set to 15 pixels). When making boundary corrections, you may want to adjust the snapping tolerances for a layer or layers. To do this, follow the steps in the table on the next page.

**Table 11: Adjust Snapping Tolerances** 



Page 48



#### 5.6.2 Standard Toolbar Buttons

The **Standard toolbar** provides the navigation tools to interact with the map and layers' attribute tables.



Figure 8. Standard Toolbar

The **Standard toolbar** actually includes several smaller toolbars. Each sub-toolbar is identified by a series of small parallel lines that precede it.



Figure 9. Sub-tool Markers

The first sub-toolbar contains the **Save** button, **Map Management** button (opens the **Map Management** dialog box), and the **Search** button. The second sub-toolbar provides tools for viewing and navigating the map in **Map View**, and the third sub-toolbar allows you to identify, select, and deselect features on the map, make measurements, create spatial bookmarks, and work with the layers' attribute tables.

You can move the location of the sub-toolbars. Simply left-click the parallel lines preceding the sub-toolbar and while holding down the mouse, drag the sub-toolbar to the location you want.

Each button on the Standard toolbar and its purpose is defined in the table below.

**Table 12: Standard Toolbar Buttons** 

Button	Name	Function / Description
	Save	Saves the current GUPS project, including any user changes to layer properties, projection, last viewed extent, and layers added.
12	Map Management	Choose your geographic participant program in GUPS and access the automatically loaded default map display layers based on the program chosen.
8	GUPS Data Settings	Warning! This tool deletes files and folders permanelty! Change GUPSGIS data working directory and clean GUPS project data.
	Search	Search the map by place, landmark, or street name and zoom automatically to the feature.
(A)	Touch Zoom and Pan	Designed for touchscreen computers. Allows you to zoom and pan the map displayed in <b>Map View</b> using finger gestures to increase or decrease the map scale.
du)	Pan Map	Shifts the map in <b>Map View</b> without changing the map scale. Click the button, then click a location on the map to re-center the map to the clicked location.
<b>*</b>	Pan Map to Selection	Shifts the map in <b>Map View</b> to the rows selected in the attribute table for a selected feature. After selecting a feature(s), click the button to re-center the map based on the selected feature(s).
<b>Æ</b>	Zoom In	Displays the map in <b>Map View</b> at a larger scale. Click the button, then click on the map at the location to which you want to zoom.
$\wp$	Zoom Out	Displays the map in <b>Map View</b> at a smaller scale.
<b>一</b> 整	Zoom Full	Displays the map in <b>Map View</b> at a smaller scale and zooms the map view to the full extent of the county.
<b>\$</b>	Zoom to Selection	Zooms the <b>Map View</b> to the rows selected by query in the attribute table for a feature(s). After selecting a feature(s) on the map, click the button to view the feature(s) at a greater map scale.
$\wp$	Zoom to Layer	Zooms the <b>Map View</b> to the layer selected in the <b>Table of Contents</b> . After selecting the layer, click the button to zoom to the layer's extent.
R	Zoom Last	Zooms the <b>Map View</b> to the previous map extent.
Æ	Zoom Next	Zooms the <b>Map View</b> forward to the next map extent (if you viewed the previous extent).
2	Refresh	Displays <b>Map View</b> to initial full display.
	Identify Features	Identifies geographic features. Click the button, then click on a feature on the map to identify the feature at the location.

Button	Name	Function / Description
	Select Features by Area or Single Click	Allows the user to select layer features in the map window with a single click, by dragging the cursor, or by drawing graphics on the screen.
		Select Feature(s)  Select Features by Polygon  Select Features by Freehand  Select Features by Radius
-	Deselect Features from All Layers	Deselects selected features from all layers.
3	Select Features Using an Expression	Initiates an attribute table record request by querying the table based on table fields and/or values in the fields.
	Measure	Provides options to measure linear distance, area, and angles on the map.
	New Bookmark	Creates and names a spatial bookmark of the current map view.
	Show Bookmarks	Display all bookmarks created by the user.


Most of the sub-toolbar buttons defined above are straight-forward. Those related to features, however, require further explanation. You will need these buttons to identify and select/deselect features on the map and to view feature attributes. You will also need them to make measurements and create spatial bookmarks.

## **Identify a Feature Using the Identify Features Button**

To identify a feature on the map, follow the steps in **Table 13** below.

**Table 13: Identify a Feature on the Map** 

Step	Action and Result
Step 1	CLICK THE <b>IDENTIFY</b> BUTTON ON THE <b>STANDARD TOOLBAR</b> .
Step 2	Then right-click on the feature. <i>The results will display in drop-down menus on the map</i> .



## Select/Deselect Features Using the Select Features and Deselect Features Buttons

The **Select Features** button gives you several ways to select features on the map. The **Deselect Features from All Layers** button allows you to deselect features you previously selected. **Table 14** describes each of the feature selection methods, discusses when one might be preferable over another, and explains how to deselect features.

**Table 14: Select/Deselect Features on the Map** 

Step	Action and Result	
Step 1	To begin, click on the layer name in the <b>Table of Contents</b> for the layer in which you want to select a feature. For example, if you want to select linear features, click on the 'edges' layer; if you want to select faces, click on the 'faces' layer.	
Step 2	Click once on the Select Features button on the Standard Toolbar.	
Step 3	To select an edge or face on the map, click on it. In this example, we have selected 'faces' in the <b>Table of Contents</b> and clicked on a face. <i>The face selected turns cyan blue (color may vary)</i> .	
Step 4	To select more than one face, hold down the <b>CTRL</b> key while clicking on the additional faces you wish to select. This method is suited to instances where you want to select faces that are not contiguous, as shown below.	
i	You can also select multiple features by simply clicking the <b>Select Feature</b> button, then dragging your cursor over the features. This method is convenient when you want to select a large number of contiguous faces or a large number of nearby linear features without having to click each, one by one.	
i	A Note on GUPS Tools	
	GUPS tools remain active until a different tool is selected. For example, if you use the <b>Select Features</b> tool to choose faces for a new area landmark, then decide you would rather add a new linear feature instead, you must click the <b>Add Linear Feature</b> tool before you click on the map again. If you do not, the <b>Select Features</b> tool, still active, selects a face.	
Step 5	To open other <b>Select Features</b> options, click on the down arrow to the right of the <b>Select Features</b> button. The <b>Select Features</b> drop-down menu opens.	


Step	Action and Result
	Click here to open menu.  Select Feature(s) Select Features by Polygon Select Features by Freehand Select Features by Radius
Step 6	The first option in the menu, 'Select Feature(s)', duplicates the functions available when you click on the main button on the toolbar.    Select Feature(s)   Select Features by Polygon   Select Features by Freehand   Select Features by Radius
Step 7	The second option, 'Select Features by Polygon', allows you to draw a polygon on the map to select features. To use this feature select it in the drop-down menu, then follow the steps below.  Select Feature(s)  Select Features by Polygon  Select Features by Freehand  Select Features by Radius
Step 8	Left-click on the map where you want to begin the polygon. Drag your cursor to extend the line to the point you want, left-click, then extend the line in a new direction. Continue until you have a closed polygon, as shown below.
Step 9	When you are done, right-click. (This tells the system you have finished drawing). All faces with an edge appearing within the polygon are highlighted in cyan blue.


Step	Action and Result
Step 10	The third option, 'Select Features by Freehand', allows you to use your cursor to draw a variety of shapes to select a face or faces.  Select Feature(s) Select Features by Polygon Select Features by Freehand Select Features by Radius
	To use this option, click on the map and use your cursor to draw any shape (polygon, triangle, circle, etc.). If the shape does not cross any edges, the single face in which the shape is drawn is selected and turns cyan blue. If the shape crosses several faces, all faces whose edges are crossed are selected and turn cyan blue.  Note: This method is particularly useful when attempting to select a very small face. You may draw a tiny triangle, for example, within a face to select it.
Step 11	The final option, 'Select Features by Radius', allows you to use your cursor to draw a circle to define the features you want to select.  Select Feature(s) Select Features by Polygon Select Features by Freehand Select Features by Radius
	To use this tool, left-click on the map where you want to begin, then hold down the mouse and drag the cursor outward to expand the circle. Release the mouse when you are done. The feature(s) selected is(are) highlighted in cyan blue.
Step 12	You can either deselect polygons selected by holding and using the same selection option to deselect by holding CTRL and retracing over the polygons, or deselect a feature or features automatically by clicking the <b>Deselect Features from All Layers</b> button (next to the <b>Select Features</b> button) once.
	The selected features in all layers are deselected.


#### **Select Features by Querying the Attribute Table**

Another method to select features is by querying the attribute table. To do so, follow the steps in **Table 15**. In this example, we are querying the attribute table for the edges layer to locate and select all linear features flagged as edges for block boundaries.

**Table 15: Select Features by Querying the Attribute Table** 









#### View an Attribute Table for a Layer on the Map

To view an attribute table for a map layer, follow the steps in the table below.

**Table 16: View Layer Attributes Using the Attributes Table** 







## **Determine Distance, Area, and Angles on the Map**


To measure the distance between two or more points, area, or an angle on a map, follow the steps in **Table 17**.

Table 17: Measure Distances, Area, and Angles on a Map







Step 3 Zoom to the map location where you want to make the measurement. Then click on the beginning point on the map and continue clicking on points until you reach the final point. Right-click when you are done. The length of each segment of the line you drew, as well as the total length of the line between the beginning point and the ending point, appear in the Measure box.



To measure area on the map, select 'Measure Area' in the drop-down menu. The Measure box opens. When the box opens, left-click on the map to begin drawing a polygon around the area you want to measure. Left-click when you reach each vertex of the polygon. When you are finished, right-click. The area polygon encompasses appears in the Total field. Use the drop-down to the right to see the area in other units of measure.




To begin a new measurement, click the **New** button.



#### Save Locations on a Map Using the Bookmark Button

To save geographic locations on your map and view them later, follow the steps in **Table 18** below.

**Table 18: Bookmark Locations on a Map** 



S	tep	Action and Result
		To delete a bookmark, click on the bookmark name, then press the <b>Delete</b> button.
	i	Bookmark names and coordinates cannot be edited from the <b>Geospatial Bookmarks</b> dialog box.

#### 5.6.3 BAS Toolbar Buttons

The **BAS toolbar** provides the BAS-specific functions needed to complete your review and update activities, as well as to import and export zipped shapefiles.



Figure 10. BAS Toolbar

Each toolbar button is described in **Table 19** below.

**Table 19: BAS Toolbar Buttons** 

Button	Name	Function/Description
+	Add Linear Feature	Add a new linear feature.
×	Delete Linear feature	Delete an existing linear feature.
⊳e	Split Linear Feature	Split a linear feature. You may need to split a linear feature to accurately reflect an entity's location. This feature "splits" the original into two.
A	Display All Names	Displays all names for a street with multiple names assigned in the MAF/TIGER System.
	User Address List	Import an address list (.csv, .txt, etc.) into GUPS.
	Modify Linear Feature Attributes	Edit attributes of a selected linear feature.
	Modify Area Feature	Make updates to legal area (annexations, deannexations, boundary corrections, etc.).
#P-1	Show/Hide Legend	Shows or hides the layer.
V	Geography Review Tool	Review the attribute table for a layer.
<u></u>	Review Change Polygons	Review change polygons in a layer and make corrections (reviews change polygons for holes and minimum size).
	Import County ZIP	Import zipped Census Bureau shapefiles shared by another GUPS user.

Button	Name	Function/Description
	Export to ZIP	Create the ZIP file containing all required data and shapefiles to be submitted to the Census Bureau.
	Print Map to File	Export a printable map in .pdf, .png, .tif, or jpeg format.
•	Add Point Landmark	Add a new point landmark.
*	Edit Point Landmark	Edit point landmark attributes.
*	Delete Point Landmark	Delete an existing point landmark.

### 5.6.4 Status Bar

The **Status bar** at the bottom of the GUPS main page displays information about the map. It allows you to adjust the map scale and see the mouse cursor's coordinates on the map.



Figure 11. Status Bar

Table 20 describes each element of the Status bar.

**Table 20: Status Bar Elements** 

Item	Description
8	Allows you to toggle between the mouse's coordinate position or the map view extents as you pan and zoom in and out on the map.
Coordinate	Shows your current position in map coordinates (default is decimal degrees for GUPS) as your map cursor is moved across the map.
Scale	Shows the current zoom level in the <b>Map View</b> . Can be changed by selecting one of the predefined levels from the drop down, by typing in a new ratio, or using the scroll wheel on your mouse.
Rotation	Shows the map rotation.
Render	Allows you to temporarily prevent layers from drawing by clicking the checkbox immediately to the left of "Render."
DEPSG:4269 (OTF)	Clicking on the icon opens the projection properties for the current map.

# 5.7 How to Import User-Provided Data into GUPS

#### 5.7.1 The Add Data Toolbar

To import your own imagery, geodatabase, shapefiles, web mapping service, or other data layers into GUPS you will use the **Add Data toolbar**.



Figure 12. Add Data Toolbar

Although shown in a horizontal position here, the **Add Data toolbar** appears arranged vertically to the left of the **Table of Contents** in GUPS. Its buttons are described in **Table 21**.

**Table 21: Add Data Toolbar Buttons** 

Button	Name	Function / Description
V.	Add Vector Layer	Allows you to add shapefile and geodatabase files to your GUPS project.
	Add Raster Layer	Allows you to add raster datasets such as imagery.
	Add PostGIS Layer	Add PostGIS layer.

Button	Name	Function / Description
Po	Add SpatialLite Layer	Add data from a SpatialLite database.
P	Add MS SQL Layer	Add MS SQL 2008 Spatial data.
	Add Oracle Spatial Layer	Add a spatial layer from an Oracle database.
	Add WMS/WM(T)S Layer	Add Web Mapping Services and Web Mapping Tile Services. Publicly accessible and secured WMS services are supported.
	Add WCS Layer	Add Web Coverage Services, which provide access to raster data useful for client-side map rendering.
	Add WFS Layer	Add Web Feature Services.
<b>V</b>	New Shapefile Layer	New Temporary Scratch Layer Ctrl+Shift+N
		Add a new shapefile layer or new temporary scratch layer.

## 5.7.2 How to Upload User-Provided Data Layers


GUPS supports vector data in a number of formats, including those supported by the OGR library data provider plugin, such as ESRI shapefiles, MapInfo MIF (interchange format), and MapInfo TAB (native format). It also supports PostGIS layers in a PostgreSQL database and SpatiaLite layers. Support for additional data types (e.g., delimited text) is provided by additional data provider plugins.

Below are the steps to import the most commonly used data formats. To upload shapefile or geodatabase data layers, follow the steps in the table below.

**Note:** You May Only Upload One User-Provided Data Layer at a Time. If you have multiple data layers that you wish to upload, note that GUPS will only allow you to upload one layer at a time.

Table 22: Load Shapefiles/Geodatabase Layers

Step	Action and Result
Step 1	Pogin the unlead. Click the Add Vector Lavor.
	Begin the upload. Click the <b>Add Vector Layer</b> button on the <b>Add Data toolbar</b> . The <b>Add Vector Layer</b> dialog box opens.



To load data from a web mapping service, follow the steps in **Table 23** below.

Table 23: Load Data from a Web Mapping Service

Step	Action and Result
Step 1	Begin the upload. Click the Add WMS/WM(T)S Layer button  The Add Layers from a WM(T)S Server dialog box opens.  on the Add Data toolbar.
Step 2	Select the web mapping service. Click the <b>Layers</b> tab, then click the <b>New</b> button under the tab. The <b>Create a new WMS Connection</b> dialog box opens.
Step 3	In the <b>Name</b> field, type a name for the web mapping imagery service. In the <b>URL</b> field, type the URL for the service. If the service requires a user name and password, type them in the fields provided. Click <b>OK</b> . The service will be added to the drop-down menu for web mapping services appearing just below the <b>Labels</b> tab. <b>Note:</b> If you are working inside a firewall, you may be prompted to enter a user name and password to obtain resources from outside the firewall.
Step 4	Select the imagery service you added in the drop-down menu. The available layers appear in the ID/Name/Title/Abstract box.
Step 5	Click on the layer you want to display, then click the <b>Add</b> button. The WMS is added to the map showing in <b>Map View</b> and to the <b>Table of Contents</b> .
i	When the WMS is added, it displays over the top of other layers you have selected for <b>Map View</b> . To make it display below these layers, click on the WMS layer and, while holding down the mouse button, drag it to the bottom of the <b>Table of Contents</b> .

If you do not have access to a web mapping service, have a poor Internet connection, or work under a restrictive firewall, you can still add other types of imagery files to GUPS (e.g., a county or state imagery dataset), one option for adding imagery may be the National Agricultural Imagery Service (NAIP), supplied in web mapping service format by the U.S. Geological Survey. To add imagery files, follow the steps in the Table 24 below.


**Table 24: Add Imagery Files** 


Step	Action and Result
Step 1	Click the Add Raster Layer button on the Add Data toolbar. The Open a GDAL Supported Raster Data Source dialog box opens.
Step 2 Step 3	Navigate to the folder on your computer where the imagery file is stored.  Select the file, then click <b>Open</b> . <i>The file loads into GUPS</i> .

### 5.7.3 How to Import a Shared ZIP Shapefile

If you want to import Census Bureau shapefiles already updated by another user, you may use the **Import Project ZIP File** button (available both on the BAS toolbar and in the Map Management dialog box), then follow the steps in **Table 25** below.

Table 25: Import a ZIP File Shared by Another User





## **SECTION 6: MAKING BAS UPDATES IN GUPS**

The tables in this section provide step-by-step instructions for making BAS updates. The examples assume you have read and understood the directions for opening GUPS and using Map Management. If you do not yet feel comfortable with Map Management, please review the contents of **Section 5: Using GUPS (Basics and Map Management)** before you begin making updates. It is highly recommended to use a souce of imagery data when making any BAS updates.

All examples shown here, although using real data, are purely fictitious. They are employed for purposes of illustration only and do not indicate any actual geographic changes.


## 6.1 How to Update Legal Boundaries


# 6.1.1 Recording an Annexation


Follow the steps in **Table 26** to record an annexation. The fictitious example in this table looks at an incorporated place named Kissimmee, Florida. Kissimmee has annexed several parcels previously outside its city limits.


Table 26: Record an Annexation


Step	Action and Result
Step 1	OPEN IN <b>MAP VIEW</b> THE COUNTY THAT CONTAINS THE PLACE (OR OTHER LEGAL ENTITY) THAT IS ANNEXING AREA. BE SURE THAT YOU HAVE ALL LAYERS YOU WISH TO SEE ON THE MAP CHECKED IN THE <b>TABLE OF CONTENTS</b> .
Step 2	Click the Modify Area Feature button on the BAS toolbar.  The Modify Area Feature dialog box opens.



















# 6.1.2 Recording a Deannexation


Follow the steps in **Table 27** to record a deannexation. The fictitious example in this table uses Sayre City, an incorporated place in Oklahoma.


Table 27: Recording a Deannexation


Step	Action and Result
Step 1	OPEN IN <b>MAP VIEW</b> THE COUNTY THAT CONTAINS THE PLACE (OR OTHER LEGAL ENTITY) THAT IS DEANNEXING AREA. BE SURE THAT YOU HAVE ALL LAYERS YOU WISH TO SEE ON THE MAP CHECKED IN THE <b>TABLE OF CONTENTS</b> .
Step 2	Click the Modify Area Feature button on the BAS toolbar.
	The Modify Area Feature dialog box opens.













# 6.1.3 Adding a New Legal Entity (New Incorporation)


Follow the steps **Table 28** to add a new legal entity. In this example, we will add a fictitious newly incorporated place in Michigan.


**Table 28: Adding a New Legal Entity** 


Step	Action and Result
Step 1	OPEN IN MAP VIEW THE COUNTY WHERE YOU WANT TO ADD A NEW ENTITY. BE SURE THAT YOU HAVE ALL LAYERS YOU WISH TO SEE CHECKED IN THE TABLE OF CONTENTS.
Step 2	CLICK THE <b>MODIFY AREA FEATURE</b> BUTTON ON THE <b>BAS TOOLBAR</b> .













### Step Action and Result Modify Area Feature 🕒 🕒 🔀 \* Indicates required field STATEFP: COUNTYFP: Bradfordville EFF\_DATE: \* 12/04/2017 AUTHTYPE: \* O - Ordinance DOCU: \* Bradfordville\_NewEnti Ok Cancel

#### Step 14 Click the OK button.

**Note:** Red asterisks indicate required fields. You must complete required fields to move forward. If you click **OK** and have not completed one or more required fields, GUPS will prompt you to do so. Any required field not completed will highlight in red, as shown below.



If you have completed all required fields, when you click OK, the faces for the new entity turn purple on the map (colors may vary) and the name of the new entity appears in the list of incorporated places in the **Modify Area Feature** dialog box.




Step	Action and Result
i	Once the Census Bureau verifies the new entity, it will assign it a FIPS code.  The code preceding the new entity name in the list is <i>not</i> a FIPS code, and <i>should not be used for any official purpose</i> . It is only a placeholder until the official FIPS code can be assigned.
Step 15	To make additional changes to the map, simply make a new selection in the <b>Modify Area Feature</b> dialog box <b>Geography</b> field and continue work. You may save your changes as you go or wait until you have finished all work on the map. Saving as changes are completed, however, is recommended to avoid losing work in the event of a power outage or system interruption.
į	New Entity that Crosses a County Boundary  If the new entity crosses a county boundary, you must add the new entity in both counties separately. After making the change in your working county, return to Map Management, select the other county as the working county, and proceed to add the new entity in this county as well. If the added entity crosses more than one county boundary, complete the addition in each county affected.


# 6.1.4 Deleting an Entity (Disincorporation)

Follow the steps in **Table 29** to record a disincorporation. In this example, we will show a fictitious disincorporation for Minersville, Utah.

**Table 29: Record a Disincorporation** 

Step	Action and Result
Step 1	OPEN IN MAP VIEW THE COUNTY THAT CONTAINS THE ENTITY YOU WISH TO DELETE. BE SURE THAT YOU HAVE ALL LAYERS YOU WISH TO SEE CHECKED IN THE TABLE OF CONTENTS.
Step 2	Click the Modify Area Feature button on the BAS toolbar.
	The <b>Modify Area Feature</b> dialog box opens.







Step	Action and Result
	select the other county as the working county, and proceed to delete the entity in this county as well. If the deleted entity crosses more than one county boundary, complete the deletion in each county affected.


### 6.1.5 Making a Boundary Update on a County Line


Users reporting on behalf of an incorporated place may make changes across county boundaries for their place. The steps in **Table 30** below provide an example for an annexation by a place across a county boundary. The fictitious example uses Brooklyn Village, in Dane County, Wisconsin. It has annexed land in adjacent Rock County.


Table 30: Record an Annexation in an Adjacent County




















#### 6.1.6 Making a Legal Boundary Change for a Consolidated City

Users who represent consolidated cities (i.e., cities that share a consolidated government with a county or minor civil division) should follow the steps described in **Table 30** in **Section 6.1.5: Making a Boundary Update on a County Line** to show boundary changes between the city and any county adjacent to it. To show boundary changes between the consolidated city itself and the entity or entities with which it shares a government, proceed as any incorporated place user would. That is, if you wish to annex land from another entity within the consolidated government area, treat it as you would any annexation within a county.

### 6.1.7 Making a Boundary Correction (Add Area/Remove Area)


To make a boundary correction that adds or removes area from an entity, follow the steps in the table below. In this fictitious example, a boundary correction is made to the city limits of Linwood, Kansas.

**Table 31: Making a Boundary Correction** 

Step	Action and Result
Step 1	Open in <b>Map View</b> the county that contains the legal entity for which you want to add or remove area. Be sure you have all layers you wish to see on the map checked in the <b>Table of Contents</b> .
Step 2	Click the Modify Area Feature button on the BAS toolbar.
	The <b>Modify Area Feature</b> dialog box opens.
	Modify Area Feature
	Geography: Select
Step 3	Click the arrow next to the <b>Geography</b> field, and select in the drop-down menu the entity type for which you want to add or remove area. In this example, we select 'Place'. <i>The Info</i>
	list populates with all incorporated places in the county for the geography chosen.
	Modify Area Feature
	Geography Place \$
	Info
	20-04400-Basehor city 20-07975-Bonner Springs city 20-19600-Easton city  List of all
	20-38650-Lansing dty incorporated places in the
	20-41475-Linwood city 20-70800-Tonganoxie city
Step 4	CLICK ON THE ROW IN THE LIST FOR THE PLACE THAT IS ADDING/REMOVING
	AREA (HERE LINWOOD). THE MAP ZOOMS TO THE PLACE SELECTED.




Step 5 Click the down arrow next to the Select Features button to select the face(s) to add or remove for the boundary correction. The Select Features drop-down menu opens.



In this example, we are adding three small faces that are difficult to select, so we opt for 'Select Features by Freehand'. This method allows us to place our cursor inside the first face and draw a tiny line. The selected face turns cyan blue (colors may vary).




To select the other faces, press the **CTRL** key, and while holding it down, repeat the action for the two remaining faces. *All three faces turn color.* 



i

**Note:** To add area, the area must be outside the selected place. To remove area, the area must be within the selected place.


**Step 6** On the **Modify Area Feature** toolbar, click on the **Add** button (to add area to the entity) or





### **6.1.8** Adding a Geographic Corridor


The steps to add a geographic corridor are shown in the table below. The fictitious example provided uses Dupont, Indiana. The steps in this table show how the city would mark the annexation of a geographic corridor along State Road 7, which in the example leads to a newly built golf course that is part of the town.


Table 32: Adding a Geographic Corridor




















# 6.1.9 Add a Geographic Offset

To create a geographic offset, follow the same steps as for a corridor (Table 32). The only difference is that geographic offsets are only on one side of the road.


# 6.2 How to Update Linear Features


# 6.2.1 Adding a Linear Feature

Follow the steps in below to add a linear feature.

Table 33: Adding a Linear Feature

Step	Action and Result
Step 1	Open in <b>Map View</b> the county that contains the entity where you want to add a linear feature. Be sure the edges layer is checked in the <b>Table of Contents</b> . Then zoom to the location on the map where you want to add the feature.
Step 2	Click on the Add Linear Feature button on the BAS toolbar.
Step 3	Left-click the mouse at the starting point of the line (A) and continue to left-click the mouse at each vertex (shape) point of the line. When you have completed the new line, right-click the mouse (B). The right-click tells GUPS you are finished drawing.






### 6.2.2 Deleting a Linear Feature

To delete a linear feature, follow the steps below.

**Table 34: Deleting a Linear Feature** 

Step	Action and <b>Result</b>
Step 1	Open in <b>Map View</b> the county that contains the entity where you want to delete a linear feature. Be sure the edges layer is checked in the <b>Table of Contents</b> . Then zoom to the location on the map where you want to delete the feature.
Step 2	Click on the <b>Delete Linear Feature</b> button on the <b>BAS toolbar</b> .
Step 3	Left-click the linear feature that you want to delete. In the example below, we clicked on an unnamed road. The clicked linear feature turns cyan blue (color may vary) and the <b>Delete</b> Linear Feature pop-up box appears, asking if you are sure you want to delete the feature.




#### 6.2.3 Restoring a Deleted Linear Feature

To restore a deleted linear feature, follow the steps below.

**Table 35: Restoring a Deleted Linear Feature** 


Step	Action and <b>Result</b>
Step 1	Open in <b>Map View</b> the county that contains the deleted linear feature. Be sure the edges layer is checked in the <b>Table of Contents</b> . Then zoom to the location on the map where the deleted feature is located.
Step 2	Left-click on the deleted feature. The deleted feature turns cyan blue (color may vary) and the <b>Delete Linear Feature</b> dialog box opens. The box asks you to confirm that you want to restore the line.





#### 6.2.4 Changing the Attributes of a Linear Feature

Follow the steps below to change the attributes (e.g., the name, MTFCC, or address range) of a linear feature.

Table 36: Changing the Attributes of a Linear Feature









# 6.3 How to Update Area Landmarks and Hydrographic Areas


### 6.3.1 Adding a New Area Landmark/Hydrographic Area


To create a new landmark or hydrographic area, follow the steps below. In this fictitious example, we will add a golf course in Jefferson County, Indiana, located northwest of Dupont Town.

Table 37: Creating a New Area Landmark/Hydrographic Area












#### 6.3.2 Deleting an Area Landmark/Hydrographic Area

To delete an area landmark or hydrographic area, follow the steps below.

Table 38: Deleting an Area Landmark/Hydrographic Area









#### 6.3.3 Adding Area to an Area Landmark or Hydrographic Area

Follow the steps below to add area to an area landmark or hydrographic area.

Table 39: Adding Area to an Area Landmark/Hydrographic Area





Step 5 To select the face(s) you want to add to the area landmark, click the Select Feature button on the Modify Area Feature toolbar.




Then click the face you want to add to the area feature. The added face turns cyan blue (color may vary). (**Note:** To select more than one face, depress the CTRL key, and while holding it down, click the other faces.)



Step 6 To add the face(s) selected, click the **Add Area** button on the **Modify Area Feature** dialog box toolbar.



The selected face is added to the area landmark and turns the same color as the other face(s) that make up the area landmark. The map also now shows the full extent of the area




### 6.3.4 Removing Area from an Area Landmark/Hydrographic Area


Follow the steps below to remove area from an area landmark or hydrographic area.

Table 40: Removing Area from an Area Landmark/Hydrographic Area


Step	Action and <i>Result</i>
Step 1	OPEN IN MAP VIEW THE COUNTY THAT CONTAINS THE AREA LANDMARK OR
	HYDROGRAPHIC AREA FROM WHICH YOU WISH TO REMOVE AREA. BE SURE THE
	'AREA_LANDMARKS' LAYER IS CHECKED IN THE TABLE OF CONTENTS.
Step 2	CLICK THE <b>MODIFY AREA FEATURE</b> BUTTON ON THE <b>BAS TOOLBAR</b> .
	THE <b>MODIFY AREA FEATURE</b> DIALOG BOX OPENS.




In the Geography field drop-down menu, select 'Area Landmark/Area Hydrography'. 'Area Landmark/Area Hydrography' populates the Geography field and a list of area landmarks and hydrological features in the county appears in the Info list.



Step 4 Select the area landmark/hydro area from which you want to remove area. *The selected entity is highlighted in the Info list and the map zooms to its location*. In this example, we have chosen Indian Lake County Park.



Step 5 To select the face(s) you want to remove from the area landmark, click the Select Feature





### 6.4 How to Update Point Landmarks

#### 6.4.1 Adding a Point Landmark

To add a point landmark, follow the steps below.

**Table 41: Adding a Point Landmark** 






#### 6.4.2 Deleting a Point Landmark

To delete a point landmark, follow the steps in **Table 42**.


**Table 42: Deleting a Point Landmark** 



### 6.4.3 Changing the Attributes of a Point Landmark

To change the attributes of a point landmark (e.g., its name, MTFCC), follow the steps below.

**Table 43: Changing the Attributes of a Point Landmark** 




#### 6.5 How to Use GUPS Review and Validation Tools

GUPS provides two tools—the **Geography Review** tool and the **Review Change Polygons** tool to help you review and validate the updates you have made in the system.


#### 6.5.1 Geography Review Tool


The **Geography Review** tool filters the map layers based on various fields in the attribute table. You can use this tool to check the changes you made to linear features, area landmarks, point landmarks, and legal boundaries anywhere within a county (you may also view the attributes of entities, features, landmarks, and boundaries you did not change). **Note:** Although this tool allows you to review your changes, you cannot use it to edit them.


Instructions for how to use the **Geography Review** tool information appear below.



**Table 44: Using the Geography Review Tool** 







### 6.5.2 Reviewing Change Polygons Tool

The **Review Change Polygons** tool allows you to view the transactions created from the edits you made to legal entities, as well as to area landmarks and hydrographic areas. You can review the transaction polygons that represent boundary changes, as well as new incorporations and disincorporations. The tool also allows you to make corrections to change polygons.


### Notes on Reviewing Change Polygons


You must run the Review Change Polygons tool before GUPS will export a file.


You must run the **Review Change Polygons** tool for each county in which you worked. For example, if you made changes to your working county, but also made changes to an adjacent county when annexing land for your county, you must run the change polygon check on **both** counties.


To use the **Review Change Polygons** tool, follow the steps below.

**Table 45: Reviewing Change Polygons** 











Step 16 Click the Fix button to repair the hole. The change polygon is corrected and the correction displays on the map (i.e., the hole is changed to the same color as the remainder of the polygon).	
Step 16 Click the Fix button to repair the hole. The change polygon is corrected and the correction displays on the map (i.e., the hole is changed to the same color as the	
correction displays on the map (i.e., the hole is changed to the same color as the	
Rock (55105)	
Step 17 Before the Find Holes check is complete, you must repeat the steps above for ear geography type for which you created change polygons.	ıch
Step 18 After you review for small areas and holes, you may also use the Review Change Polygons tool to check the general accuracy of your change polygons. To do so, your entity type in the Geography drop-down menu. A full list of change polygons geography type selected displays in the Info list.	select
Step 19 Click on the row for each polygon to see it on the map and review your changes.	
If you notice a mistake on the map (e.g., you created a new incorporated place the supposed to have six faces, but you selected only five), click on the <b>Modify Area</b> Feature button on the BAS toolbar and make the correction.	at was
To review boundary changes, select the entity type you want to review in the <b>Geography</b> drop-down menu at the top of the <b>Review Change Polygons</b> dialog this example, we select ' <b>Place</b> '. All boundary change polygons for the entity type selected populate the <b>Info</b> list.  To review a boundary change, click on the change polygon in the list, then click the	





### Step 23


IN THE **DOCU** FIELD, TYPE IN THE ORDINANCE OR OTHER LEGAL DOCUMENTATION NUMBER AUTHORIZING THE ANNEXATION, OR UPLOAD LEGAL DOCUMENTATION FOR THE CHANGE. TO UPLOAD DOCUMENTATION, CLICK THE FOLDER ICON NEXT TO THE **DOCU** FIELD.




WHEN THE **DOCU** WINDOW OPENS, CLICK ON THE ICON FOR 'MY COMPUTER' (OR SIMPLY 'COMPUTER' IN SOME WINDOWS VERSIONS) TO OPEN THE DIRECTORY WHERE YOU HAVE SAVED YOUR DOCUMENTATION.



YOUR DIRECTORIES DISPLAY, AS SHOWN BELOW.



Select the appropriate directory and navigate to the file you want to upload. Click the file. Then, to upload it, click the **Open** button at the bottom of the **DOCU** window.



GUPS uploads the file and the file name appears in the DOCU field.


Step	Action and <b>Result</b>	
Step 24	Finally, in the <b>CHNG_TYPE</b> field drop-down menu, change 'Boundary Correction' to the correct change type ('Annexation', 'Corridor', or 'Offset'). Here we select 'Annexation'.	
	DOCU: * Select Annexation Boundary Correction New Entity Corridor Offset	
Step 25	Click the <b>OK</b> button. <i>The correction is made</i> .	
Step 26	When you have completed <i>all your reviews</i> (for small areas, holes, and boundary changes) for <i>all entity types</i> , and have made any corrections needed, click the <b>Save</b> button on the <b>BAS toolbar</b> . <i>All corrections are saved. Your Review Change Polygons check is complete.</i>	
Step 27	If you made changes in more than one working county, return to <b>Map Management</b> , select the additional county as your working county, and repeat the steps above. Repeat this process as many times as needed until you have run the <b>Review Change Polygons</b> check on all the counties in which you made changes.	


## 6.6 Export a Printable Map


GUPS allows you to generate printable maps in four formats (.pdf, .png., .tiff, and .jpeg). The maps can be created in portrait or landscape view, on letter or ledger (legal) size paper, and at various scales. To export a printable map from GUPS, follow the steps below.

Step Action and **Result** Click on the Export to ZIP button on the BAS toolbar. Step 1 The **Print Map to File** dialog box opens. Print Map to File **Desired Map Titles:** Map Title (30 char max): Map Sub-Title (30 char max): **Page Orientation:** Portrait Landscape Map Scale: Match Current Map Extent ○ Fixed Scale: 1:1,000,000 \$ Desired Page Size: **Export File Format:** Letter (8.5x11 inch) O Ledger (11x17 inch) Export as PDF O ANSI-C (17x22 inch) Export as PNG Image O ANSI-D (22x34 inch) Export as TIFF Image O ANSI-E (34x44 inch) Export as JPEG Image **■** Save **X** Cancel Step 2 In the **Desired Map Titles** section, type in a map title and sub-title. Print Map to File X Desired Map Titles: Map Title (30 char max): 55105\_Dane\_County\_W1\_Shapefile Map Sub-Title (30 char max): Edges Layer Step 3 Under Page Orientation, click the radio button next to 'Portrait' or 'Landscape' to select the map's orientation on the page when printed.

**Table 46: Export a Printable Map** 







### 6.7 How to Export ZIP Files to Share/Submit

When creating ZIP files to export, you have two options—you may export the file to share with another user or you may export the file for submission to the Census Bureau. In either case, GUPS automatically names the output ZIP file for you. It packages all the files required by the Census Bureau (including any documentation you uploaded) into the ZIP file and saves it in a preset location created on your computer by during the installation process.

#### Important Note


If you make changes to more than one working county, you must export a separate ZIP file for each.


# 6.7.1 Exporting a File to Share

To export a file to share with another user, follow the steps below.

Table 47: Exporting Files to Share with Another User

Step	Action and <b>Result</b>	
Step 1	Click on the <b>Export to ZIP</b> button on the <b>BAS toolbar</b> .	
Step 2	After you click <b>Export to Zip</b> button, you may receive one of two results, depending on whether you have validated your changes using the <b>Review Change Polygons</b> tool. If you have not used the tool to check your work, the <b>Export to ZIP</b> pop-up box appears and lists the specific checks that need to be run before you can export the file.	








### 6.7.2 Exporting a File to Submit to the Census Bureau

To export a file to submit to the Census Bureau, follow the steps below.

Table 48: Exporting Files for Submission to the Census Bureau








# SECTION 7: SUBMITTING YOUR FILES TO THE CENSUS BUREAU THROUGH SWIM


To upload and transmit your update files to the Census Bureau, you must access your account in the Secure Web Incoming Module (SWIM), as shown in the table below.


**Note:** If you **already have a SWIM account**, have your user name (email address) and password ready. If you **do not have a SWIM account**, have the 12-digit registration token provided by the Census Bureau ready.


Table 49: Transmitting Files to the Census Bureau Using SWIM



Step	Action and <b>Result</b>			
	Account Registration			
	Registration Token:			
	First Name:			
	Last Name:			
	Phone Number:	#		
	Agency:			
	Email:			
	Confirm Email:			
	Password:			
	Confirm Password:			
	Security Question:	Please select a verification question.		
	Answer:			
	Submit			
i	All fields on the <b>Account Registration</b> screen are required. You will not be able to move to the next screen until you have completed all fields.			
Step 3	On the <b>Account Registration</b> screen, first, enter the 12-digit token provided by the Census Bureau. Then enter your name, agency, and email in the appropriate fields.			
Step 4	Next, create a password. The passwords must meet the five criteria below:			
	It must be 8 characters in length			
	2. It must have at least one upper case character			
	3. It must have at least one lower case character			
	4. It must have at least one number	SPECIAL CHARACTER (VALID SPECIAL		
	CHARACTERS ARE: #, !, \$, *, &,	?, ~). <b>NOTE:</b> COMMAS IN THE SPECIAL PACING PURPOSES ONLY; THE COMMA IS NOT A		
Step 5	Set up a security question (click the arrow on the right of the <b>Security Question</b> box and select a question in the drop-down list, then enter an answer in the <b>Answer</b> box). When you have finished, click the <b>Submit</b> button. A screen opens to confirm that you have successfully registered.			







Step	Action and <i>Result</i>		
	Thank You  Your files have uploaded successfully.  File(s):  1. bas18_10200016980_return.zip  2. bas18_21807700000_DataDirectory.zip  You may Log Out or return to the upload form, to submit more files.		
Step 16	TO SUBMIT FILES FOR A DIFFERENT ENTITY, CLICK ON THE 'UPLOAD FORM' LINK IN THE PHRASE "YOU MAY LOG OUT OR RETURN TO THE UPLOAD FORM, TO SUBMIT MORE FILES." THIS CHOICE RETURNS YOU TO THE WELCOME SCREEN.		
	TO LOG OUT, CLICK ON <b>LOG OUT</b> . THE CENSUS BUREAU WILL ACKNOWLEDGE THE RECEIPT OF THE UPLOADED FILE.		
i	SWIM sessions deactivate after 15 minutes of inactivity.  Note: While working in SWIM, you may obtain help by clicking on the Help button on any screen. When you click the button, a screen opens with links to help resources.		
	SWIM - Secure Web Incoming Module  Already Registered? Login Help		
	Help		
	The Secure Web Incoming Module (SWIM) is a single upload page for submitting all local geographic partnership data to the U.S. Census Bureau's Geography Division. Because of the wide variety of geographic partnership programs, the SWIM requires users to answer some basic questions about their data before submitting. These questions direct the incoming data to the right partnership program.		
	The general flow of questions is as follows:		
	1. What geographic partnership program you are submitting data for? 2. What level of government or organization is submitting the data? Many of our geographic programs allow partners from various levels of governments to submit data, which is represented as a geographic entity in the menu selection. For example, when submitting data on behalf of a state government, the submitting entity is the state, even if the data submitted pertains to some other entity within the state, such as a county. 3. What is the name of your entity? A user can select an entity's name from pre-populated drop-down boxes.		
	After completing the above questions, the user must select a ZIP file to upload. Using a ZIP archive ensures an efficient upload of all submitted files.  There are many compression software options where one can do this with relative ease.		
	For more information about the Census Bureau's Geography Division, please visit our Geography Homepage.		
	For more information about our geographic partnership programs at the Census, please visit our Partnerships Homepage.		
	For a glossary of common Census Geography Terms and Concepts, please visit our Terms and Concepts page.		

# **APPENDICES**

# APPENDIX A. BAS CONTACT INFORMATION AND RESOURCES

Action/Question	Resource	Contact
Request shapefiles on DVD	Geography Division	Call: 1-800-972-5651 EMAIL: <u>GEO.BAS@CENSUS.GOV</u>
BAS materials questions	Geography Division	Call: 1-800-972-5651 EMAIL: <u>GEO.BAS@CENSUS.GOV</u>
Legal boundary questions	Geography Division	Call: 1-301-763-1099 EMAIL: <u>GEO.BAS@CENSUS.GOV</u> Fax: 1-800-972-5652
Ask guidance on areas under legal dispute	Census Bureau Legal Office	Call: 1-301-763-9844
GUPS technical support	Geography Division	Call: 1-800-972-5651 EMAIL: <u>GEO.BAS@CENSUS.GOV</u>
		Be sure to have the number for the version of GUPS you are running ready. To find this number, go to the <b>Help</b> tab on the main <b>Menu</b> in GUPS and click 'About GUPS' in the dropdown menu. A pop-up box will provide you the number.
SWIM token questions	Geography Division	Call: 1-800-972-5651 EMAIL: <u>GEO.BAS@CENSUS.GOV</u>
SWIM technical support	Geography Division	GEO.SWIM@CENSUS.GOV
Submit output files on DVD (if you do not have Internet access)	National Processing Center	Send to:  US Census Bureau National Processing Center ATTN: BAS Returns, Bldg 63E 1201 East 10th Street Jeffersonville, IN 47132

### APPENDIX B. TERMS

**Areal Feature** - is a prominent and identifying feature of a landscape significant enough to warrant name recognition, such as a lake, park, school, military base, or cemetery, etc. This type of feature class is only assigned to a face geometry. Any face can be assigned to multiple features. For example, a water body can also be part of a park.

Edge - is a one-dimensional object (legacy 1-cell), bounded by two nodes: a start node and an end node. Its geometry is distinguished by the coordinates of the start and end nodes, and additional coordinates that are ordered and serve as vertices (or shape points) between the two nodes. An edge is a primitive feature in the Oracle database.

Effects of having **Edge** features in the MAF/TIGER Database(MTDB):

- Represents an invisible boundary line for various geometry, geographic, and statistical data and can stand alone.
- A linear feature always occupies the same space as an edge and there are attributes on an edge that are lone relevant when a linear feature exists.

Face - is a two-dimensional object (legacy 2-cell) bounded by two or more edges. Its boundary includes not only the edges that separate it from other faces, but also any interior edges (twodimensional topological primitives) contained within the area of the face.

Geographic Area - is a demarcated area used for the collection and/or tabulation of Census Bureau data.

Geographic Corridors - is an area that includes only a road (or other feature's) rightof-way and does not contain any structures. Figure 13. Annexed Area Corridor and **Unincorporated** shows a corridor that has been created where an incorporated place annexed the road right-of-way, but not the housing units assigned to either side of the road (these belong instead to an unincorporated area). If it is important to the incorporated place that its ownership and/or maintenance of the road and/or its right-ofway be displayed on Census Bureau's maps, a geographic corridor should be created. However, the Census Bureau does not require places to report rights-of-way: maintaining geographic corridors in a nationwide database is difficult and impractical, and the right-of-way should only be included if it is crucial to the place, or if state or local laws require it. The Census Bureau would actually prefer that the area simply not be assigned to the place at all.

Figure 14. shows an example where the right-of-way belongs in an unincorporated area, while the housing units along it are included in an incorporated place (shown in color). While depicting this corridor may be important for local purposes, it is not

relevant for Census Bureau tabulations and is not easy to depict in the Census nationwide database. This type of corridor should not be included in a BAS response.

Please note that the Census Bureau does not require places to display rights-of-way or road maintenance corridors that do not contain or potentially contain housing or population. If local or state law does not require depiction of these geographic features, the Census Bureau prefers that they be left off BAS submissions. However, if it is necessary for the place to depict them, then they must be submitted as a geographic corridor.




Figure 13. Annexed Area Corridor and Unincorporated Area

**Figure 13** - A corridor that has been created where an incorporated place annexed the road right-of-way, but not the housing units assigned to either side of the road.




Figure 14. Incorporated Area and Unincorporated Area

**Figure 14** - The right-of-way belongs in an unincorporated area, while the housing units along it are included in an incorporated place.

To recap, when a participant has a case where a road right-of-way is legally included in the boundary, but the adjacent parcels/houses are not, there are two options. You should either not include the area in the place at all (Scenario A in **Figure 15**. **Participant Responses**), or include it in the place and flag it as a corridor (Scenario C

in **Figure 15. Participant Responses**). What you should never do is include such areas within the place boundary without flagging them as corridors (Scenario B in **Figure 15. Participant Responses**).




Figure 15. Participant Responses

**Figure 15** – (A): The respondent did not include place ownership of the road or the right-of-way, allowing houses along the road to be geocoded correctly. (B): The respondent chose to show place ownership of the road, but did not flag it as a corridor, causing houses along the road to be incorrectly geocoded.(C): The respondent chose to show place ownership of the road, and flagged that ownership as a corridor, allowing the houses to be geocoded correctly. Both A and C are acceptable.

### Geographic Offsets

A geographic offset is an area (either within or outside of a geographic entity) that is only on one side of a road (unlike corridors, which involve both sides of the road) and does not include structures addressed to that side of the road. Much of the same guidelines regarding corridors also holds true for offsets.

The Census Bureau is aware that many governments base their legal boundaries on cadastral (parcel-based) right-of-way mapping. Census Bureau maps are based on spatial data that is topologically integrated which makes maintenance of geographic offsets inefficient. Using the road centerline wherever possible will help to establish more accurate population counts. If a boundary follows a front lot line, the Census Bureau strongly prefers that the road centerline be used as the boundary. If a boundary is at the rear of a lot, then it should be depicted as such. If it is unclear whether a particular line is a front lot line or something else, please contact the BAS team for assistance. As a rule, if a house or building could not conceivably be built in the area between the potential line and the centerline of the road, then the line can be considered a front lot line. Figure 16. A Cadastral (Parcel-Based) Boundary Map depicts a cadastral (parcel-based) boundary map and Figure 17. How a Boundary Should be Represented When Sent to the Census Bureau shows how the boundary should be represented when it is sent to the Census Bureau.




Figure 16. A Cadastral (Parcel-Based) Boundary Map




Figure 17. How a Boundary Should be Represented When Sent to the Census Bureau





Figure 18. Place Boundary - Front Lot Line

**Figure 18 -** Shows a situation in which the place boundary is along the front lot line. In this example, the respondent must either use the road centerline as the boundary (preferred), or create an offset.



#### Figure 19. Place Boundary - Rear Lot Line

**Figure 19 -** The place boundary is on the rear lot line, so the respondent should of course not use the road centerline or create an offset, but should rather digitize in a new boundary following the rear lot line.

The Census Bureau has included an "offset" shapefile in the BAS materials (bas\_2019\_offset\_<ssccc>.shp), so that your jurisdiction can be checked for any existing corridors or offsets. While the Census Bureau prefers that new offsets are not created (see above), this information can be helpful in determining if current boundaries are correct.

**Linear Feature** - is a single dimension feature (Road/Path, Hydro, Rail, or Miscellaneous) along one or more edges.

**Point Feature** - is an isolated node not connected to an edge. The XY coordinate point is where a structure resides. Point Feature structures include housing units and legacy point landmark of public facilities such as libraries, police stations, schools, churches, malls, and some monuments.

# APPENDIX C. MTFCC DESCRIPTIONS

The MAF/TIGER Feature Classification Code (MTFCC) is a 5-digit code assigned by the Census Bureau to classify and describe geographic objects or features in Census Bureau MAF/TIGER products.

MTFCC	Feature Class	Feature Class Description
C3022	Mountain Peak or Summit	A prominent elevation rising above the surrounding level of the Earth's surface.
C3023	Island	An area of dry or relatively dry land surrounded by water or low wetland [including archipelago, atoll, cay, hammock, hummock, isla, isle, key, moku and rock].
C3024	Levee	An embankment flanking a stream or other flowing water feature to prevent overflow.
C3026	Quarry (not water- filled), Open Pit Mine or Mine	An area from which commercial minerals are or were removed from the Earth; not including an oilfield or gas field.
C3027	Dam	A barrier built across the course of a stream to impound water and/or control water flow.
C3061	Cul-de-sac	An expanded paved area at the end of a street used by vehicles for turning around. For mapping purposes, the Census Bureau maps it only as a point feature.
C3062	Traffic Circle	A circular intersection allowing for continuous movement of traffic at the meeting of roadways.
C3066	Gate	A movable barrier across a road.
C3067	Toll Booth	A structure or barrier where a fee is collected for using a road.
C3071	Lookout Tower	A manmade structure, higher than its diameter, used for observation.
C3074	Lighthouse Beacon	A manmade structure, higher than its diameter, used for transmission of light and possibly sound generally to aid in navigation.
C3075	Tank/Tank Farm	One or more manmade structures, each higher than its diameter, used for liquid (other than water) or gas storage or for distribution activities.
C3076	Windmill Farm	One or more manmade structures used to generate power from the wind.
C3077	Solar Farm	One or more manmade structures used to generate power from the sun.
C3078	Monument or Memorial	A manmade structure to educate, commemorate, or memorialize an event, person, or feature.
C3079	Boundary Monument Point	A material object placed on or near a boundary line to preserve and identify the location of the boundary line on the ground.
C3080	Survey Control Point	A point on the ground whose position (horizontal or vertical) is known and can be used as a base for additional survey work.
C3081	Locality Point	A point that identifies the location and name of an unbounded locality (e.g., crossroad, community, populated place or locale).
C3085	Alaska Native Village Official Point	A point that serves as the core of an Alaska Native village and is used in defining Alaska Native village statistical areas.

MTFCC	Feature Class	Feature Class Description
G2100	American Indian Area	A legally defined state- or federally recognized reservation and/or off-reservation trust land (excludes statistical American Indian areas).
G2120	Hawaiian Home Land	A legal area held in trust for the benefit of Native Hawaiians.
G2130	Alaska Native Village Statistical Area	A statistical geographic entity that represents the residences, permanent and/or seasonal, for Alaska Natives who are members of or receiving governmental services from the defining legal Alaska Native Village corporation.
G2140	Oklahoma Tribal Statistical Area	A statistical entity identified and delineated by the Census Bureau in consultation with federally recognized American Indian tribes that have no current reservation, but had a former reservation in Oklahoma.
G2150	State-designated Tribal Statistical Area	A statistical geographic entity identified and delineated for the Census Bureau by a state-appointed liaison for a state-recognized American Indian tribe that does not currently have a reservation and/or lands in trust.
G2160	Tribal Designated Statistical Area	A statistical geographic entity identified and delineated for the Census Bureau by a federally recognized American Indian tribe that does not currently have a reservation and/or off-reservation trust land.
G2170	American Indian Joint Use Area	An area administered jointly and/or claimed by two or more American Indian tribes.
G2200	Alaska Native Regional Corporation	Corporate entities established to conduct both business and nonprofit affairs of Alaska Natives pursuant to the Alaska Native Claims Settlement Act of 1972 (Public Law 92-203). There are twelve geographically defined ANRCs and they are all within and cover most of the State of Alaska (the Annette Island Reservean American Indian reservation-is excluded from any ANRC). The boundaries of ANRCs have been legally established.
G2300	Tribal Subdivision	Administrative subdivisions of federally recognized American Indian reservations, off-reservation trust lands, or Oklahoma tribal statistical areas (OTSAs). These entities are internal units of self-government or administration that serve social, cultural, and/or economic purposes for the American Indians on the reservations, off-reservation trust lands, or OTSAs.
G2400	Tribal Census Tract	A relatively small and permanent statistical subdivision of a federally recognized American Indian reservation and/or off-reservation trust land, delineated by American Indian tribal participants or the Census Bureau for the purpose of presenting demographic data.
G2410	Tribal Block Group	A cluster of census blocks within a single tribal census tract delineated by American Indian tribal participants or the Census Bureau for the purpose of presenting demographic data.
G3100	Combined Statistical Area	A grouping of adjacent metropolitan and/or micropolitan statistical areas that have a degree of economic and social integration, as measured by commuting.
G3110	Metropolitan and Micropolitan Statistical Area	An area containing a substantial population nucleus together with adjacent communities having a high degree of economic and social integration with that core, as measured by commuting. Defined using whole counties and equivalents.
G3120	Metropolitan Division	A county or grouping of counties that is a subdivision of a

MTFCC	Feature Class	Feature Class Description
		Metropolitan Statistical Area containing an urbanized area with a population of 2.5 million or more.
G3200	Combined New England City and Town Area	A grouping of adjacent New England city and town areas that have a degree of economic and social integration, as measured by commuting.
G3210	New England City and Town Metropolitan and Micropolitan Statistical Area	An area containing a substantial population nucleus together with adjacent communities having a high degree of economic and social integration with that core, as measured by commuting. Defined using Minor Civil Divisions (MCDs) in New England.
G3220	New England City and Town Division	A grouping of cities and towns in New England that is a subdivision of a New England City and Town Area containing an urbanized area with a population of 2.5 million or more.
G3500	Urban Area	Densely settled territory that contains at least 2,500 people. The subtypes of this feature are Urbanized Area (UA), which consists of 50,000 + people and Urban Cluster, which ranges between 2,500 and 49,999 people.
G4000	State or Equivalent Feature	The primary governmental divisions of the United States. The District of Columbia is treated as a statistical equivalent of a state for census purposes, as is Puerto Rico.
G4020	County or Equivalent Feature	The primary division of a state or state equivalent area. The primary divisions of 48 states are termed County, but other terms are used such as Borough in Alaska, Parish in Louisiana, and Municipio in Puerto Rico. This feature includes independent cities, which are incorporated places that are not part of any county.
G4040	County Subdivision	The primary divisions of counties and equivalent features for the reporting of Census Bureau data. The subtypes of this feature are Minor Civil Division, Census County Division/Census Subarea, and Unorganized Territory. This feature includes independent places, which are incorporated places that are not part of any county subdivision.
G4050	Estate	Estates are subdivisions of the three major islands in the United States Virgin Islands (USVI).
G4060	Subbarrio (Subminor Civil Division)	Legally defined divisions (subbarrios) of minor civil divisions (barrios-pueblo and barrios) in Puerto Rico.
G4110	Incorporated Place	A legal entity incorporated under state law to provide general- purpose governmental services to a concentration of population. Incorporated places are generally designated as a city, borough, municipality, town, village, or, in a few instances, have no legal description.
G4120	Consolidated City	An incorporated place that has merged governmentally with a county or minor civil division, but one or more of the incorporated places continues to function within the consolidation. It is a place that contains additional separately incorporated places.
G4210	Census Designated Place	A statistical area defined for a named concentration of population and the statistical counterpart of an incorporated place.
G4300	Economic Census Place	The lowest level of geographic area for presentation of some types of Economic Census data. It includes incorporated places,

MTFCC	Feature Class	Feature Class Description
		consolidated cities, census designated places (CDPs), minor civil divisions (MCDs) in selected states, and balances of MCDs or counties. An incorporated place, CDP, MCD, or balance of MCD qualifies as an economic census place if it contains 5,000 or more residents, or 5,000 or more jobs, according to the most current data available.
G5020	Census Tract	Relatively permanent statistical subdivisions of a County or equivalent feature delineated by local participants as part of the Census Bureau's Participant Statistical Areas Program.
G5030	Block Group	A cluster of census blocks having the same first digit of their four-digit identifying numbers within a Census Tract. For example, block group 3 (BG 3) within a Census Tract includes all blocks numbered from 3000 to 3999.
G5035	Block Area Grouping	A user-defined group of islands forming a single census tabulation block. A BAG must: (1) consist of two or more islands, (2) have a perimeter entirely over water, (3) not overlap, and (4) not cross the boundary of other tabulation geographies, such as county or incorporated place boundaries.
G5040	Tabulation Block	The lowest-order census defined statistical area. It is an area, such as a city block, bounded primarily by physical features but sometimes by invisible city or property boundaries. A tabulation block boundary does not cross the boundary of any other geographic area for which the Census Bureau tabulates data. The subtypes of this feature are Count Question Resolution (CQR), current, and census.
G5200	Congressional District	The 435 areas from which people are elected to the U.S. House of Representatives. Additional equivalent features exist for state equivalents with nonvoting delegates or no representative. The subtypes of this feature are 106th, 107th, 108th, 109th, and 111th Congressional Districts, plus subsequent Congresses.
G5210	State Legislative District (Upper Chamber	Areas established by a state or equivalent government from which members are elected to the upper or unicameral chamber of a state governing body. The upper chamber is the senate in a bicameral legislature, and the unicameral case is a single house legislature (Nebraska).
G5220	State Legislative District (Lower Chamber)	Areas established by a state or equivalent government from which members are elected to the lower chamber of a state governing body. The lower chamber is the House of Representatives in a bicameral legislature.
G5240	Voting District	The generic name for the geographic features, such as precincts, wards, and election districts, established by state, local, and tribal governments for the purpose of conducting elections.
G5400	Elementary School District	A geographic area within which officials provide public elementary grade-level educational services for residents.
G5410	Secondary School District	A geographic area within which officials provide public secondary grade-level educational services for residents.
G5420	Unified School District	A geographic area within which officials provide public educational services for all grade levels for residents.
G6120	Public-Use Microdata Area	A decennial census area with a population of at least 100,000 or more persons for which the Census Bureau provides selected

MTFCC	Feature Class	Feature Class Description
		extracts of household-level data that are screened to protect confidentiality.
G6300	Traffic Analysis District	An area delineated by Metropolitan Planning Organizations (MPOs) and state Departments of Transportation (DOTs) for tabulating journey-to-work and place-of-work data. A Traffic Analysis District (TAD) consists of one or more Traffic Analysis Zones (TAZs).
G6320	Traffic Analysis Zone	An area delineated by Metropolitan Planning Organizations (MPOs) and state Departments of Transportation (DOTs) for tabulating journey-to-work and place-of-work data.
G6330	Urban Growth Area	An area defined under state authority to manage urbanization that the Census Bureau includes in the MAF/TIGER® System in agreement with the state.
G6350	ZIP Code Tabulation Area (Five-Digit)	An approximate statistical-area representation of a U.S. Postal Service (USPS) 5-digit ZIP Code service area.
G6400	Commercial Region	For the purpose of presenting economic statistical data, municipios in Puerto Rico are grouped into commercial regions.
H1100	Connector	A known, but nonspecific, hydrographic connection between two nonadjacent water features.
H2025	Swamp/Marsh	A poorly drained wetland, fresh or saltwater, wooded or grassy, possibly covered with open water [includes bog, cienega, marais and pocosin].
H2030	Lake/Pond	A standing body of water that is surrounded by land.
H2040	Reservoir	An artificially impounded body of water.
H2041	Treatment Pond	An artificial body of water built to treat fouled water.
H2051	Bay/Estuary/Gulf/ Sound	A body of water partly surrounded by land [includes arm, bight, cove and inlet].
H2053	Ocean/Sea	The great body of salt water that covers much of the earth.
H2060	Gravel Pit/Quarry filled with water	A body of water in a place or area from which commercial minerals were removed from the Earth.
H2081	Glacier	A body of ice moving outward and down slope from an area of accumulation; an area of relatively permanent snow or ice on the top or side of a mountain or mountainous area [includes ice field and ice patch].
H3010	Stream/River	A natural flowing waterway [includes anabranch, awawa, branch, brook, creek, distributary, fork, kill, pup, rio, and run].
H3013	Braided Stream	A natural flowing waterway with an intricate network of interlacing channels.
H3020	Canal, Ditch or Aqueduct	An artificial waterway constructed to transport water, to irrigate or drain land, to connect two or more bodies of water, or to serve as a waterway for watercraft [includes lateral].
K1225	Crew-of-Vessel Location	A point or area in which the population of military or merchant marine vessels at sea are assigned, usually being at or near the home port pier.
K1231	Hospital/Hospice/ Urgent Care Facility	One or more structures where the sick or injured may receive medical or surgical attention [including infirmary].
K1235	Juvenile Institution	A facility (correctional and non-correctional) where groups of juveniles reside; this includes training schools, detention centers, residential treatment centers and orphanages.

MTFCC	Feature Class	Feature Class Description
K1236	Local Jail or Detention Center	One or more structures that serve as a place for the confinement of adult persons in lawful detention, administered by a local (county, municipal, etc.) government.
K1237	Federal Penitentiary, State Prison, or Prison Farm	An institution that serves as a place for the confinement of adult persons in lawful detention, administered by the federal government or a state government.
K1238	Other Correctional Institution	One or more structures that serve as a place for the confinement of adult persons in lawful detention, not elsewhere classified or administered by a government of unknown jurisdiction.
K1239	Convent, Monastery, Rectory, Other Religious Group Quarters	One or more structures intended for use as a residence for those having a religious vocation.
K1246	Community Center	Community Center.
K2110	Military Installation	An area owned and/or occupied by the Department of Defense for use by a branch of the armed forces (such as the Army, Navy, Air Force, Marines, or Coast Guard), or a state owned area for the use of the National Guard.
K2165	Government Center	A place used by members of government (either federal, state, local, or tribal) for administration and public business.
K2167	Convention Center	An exhibition hall or conference center with enough open space to host public and private business and social events.
K2180	Park	Parkland defined and administered by federal, state, and local governments.
K2181	National Park Service Land	Area—National parks, National Monuments, and so forth—under the jurisdiction of the National Park Service.
K2182	National Forest or Other Federal Land	Land under the management and jurisdiction of the federal government, specifically including areas designated as National Forest, and excluding areas under the jurisdiction of the National Park Service.
K2183	Tribal Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of an American Indian tribe.
K2184	State Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of a state government.
K2185	Regional Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of a regional government.
K2186	County Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of a county government.
K2187	County Subdivision Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of a minor civil division (town/township) government.
K2188	Incorporated Place Park, Forest, or Recreation Area	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of a municipal government.
K2189	Private Park, Forest, or Recreation Area	A privately owned place or area set aside for recreation or preservation of a cultural or natural resource.

MTFCC	Feature Class	Feature Class Description
K2190	Other Park, Forest, or Recreation Area (quasi-public, independent park, commission, etc.)	A place or area set aside for recreation or preservation of a cultural or natural resource and under the administration of some other type of government or agency such as an independent park authority or commission.
K2191	Post Office	An official facility of the U.S. Postal Service used for processing and distributing mail and other postal material.
K2193	Fire Department	Fire Department.
K2194	Police Station	Police Station.
K2195	Library	Library.
K2196	City/Town Hall	City/Town Hall.
K2400	Transportation Terminal	A facility where one or more modes of transportation can be accessed by people or for the shipment of goods; examples of such a facility include marine terminal, bus station, train station, airport and truck warehouse.
K2424	Marina	A place where privately owned, light-craft are moored.
K2432	Pier/Dock	A platform built out from the shore into the water and supported by piles. This platform may provide access to ships and boats, or it may be used for recreational purposes.
K2451	Airport or Airfield	A manmade facility maintained for the use of aircraft [including airstrip, landing field and landing strip].
K2452	Train Station, Trolley or Mass Transit Rail Station	A place where travelers can board and exit rail transit lines, including associated ticketing, freight, and other commercial offices.
K2453	Bus Terminal	A place where travelers can board and exit mass motor vehicle transit, including associated ticketing, freight, and other commercial offices.
K2454	Marine Terminal	A place where travelers can board and exit water transit or where cargo is handled, including associated ticketing, freight, and other commercial offices.
K2455	Seaplane Anchorage	A place where an airplane equipped with floats for landing on or taking off from a body of water can debark and load.
K2456	Airport—Intermodal Transportation Hub/Terminal	A major air transportation facility where travelers can board and exit airplanes and connect with other (i.e. non-air) modes of transportation.
K2457	Airport—Statistical Representation	The area of an airport adjusted to include whole 2000 census blocks used for the delineation of urban areas
K2458	Park and Ride Facility/Parking Lot	A place where motorists can park their cars and transfer to other modes of transportation.
K2459	Runway/Taxiway	A fairly level and usually paved expanse used by airplanes for taking off and landing at an airport.
K2460	Helicopter Landing Pad	A fairly level and usually paved expanse used by helicopters for taking off and landing.
K2540	University or College	A building or group of buildings used as an institution for post- secondary study, teaching, and learning [including seminary].
K2543	School or Academy	A building or group of buildings used as an institution for preschool, elementary or secondary study, teaching, and learning [including elementary school and high school].
K2545	Museum, Visitor Center, Cultural	An attraction of historical, cultural, educational or other interest that provides information or displays artifacts.

MTFCC	Feature Class	Feature Class Description	
	Center, or Tourist Attraction		
K2561	Golf Course	A place designed for playing golf.	
K2582	Cemetery	A place or area for burying the dead [including burying ground and memorial garden].	
K2586	Zoo	A facility in which terrestrial and/or marine animals are confined within enclosures and displayed to the public for educational, preservation, and research purposes.	
K3544	Place of Worship	A sanctified place or structure where people gather for religious worship; examples include church, synagogue, temple, and mosque.	
L4010	Pipeline	A long tubular conduit or series of pipes, often underground, with pumps and valves for flow control, used to transport fluid (e.g., crude oil, natural gas), especially over great distances.	
L4020	Powerline	One or more wires, often on elevated towers, used for conducting high-voltage electric power.	
L4031	Aerial Tramway/Ski Lift	A conveyance that transports passengers or freight in carriers suspended from cables and supported by a series of towers.	
L4110	Fence Line	A man-made barrier enclosing or bordering a field, yard, etc., usually made of posts and wire or wood, used to prevent entrance, to confine, or to mark a boundary.	
L4121	Ridge Line	The line of highest elevation along a ridge.	
L4125	Cliff/Escarpment	A very steep or vertical slope [including bluff, crag, head, headland, nose, palisades, precipice, promontory, rim and rimrock].	
L4130	Point-to-Point Line	A line defined as beginning at one location point and ending at another, both of which are in sight.	
L4140	Property/Parcel Line (Including PLSS)	This feature class may denote a nonvisible boundary of either public or private lands (e.g., a park boundary) or it may denote a Public Land Survey System or equivalent survey line.	
L4150	Coastline	The line that separates either land or Inland water from Coastal, Territorial or Great Lakes water. Where land directly borders Coastal, Territorial or Great Lakes water, the shoreline represents the Coastline. Where Inland water (such as a river) flows into Coastal, Territorial or Great Lakes water, the closure line separating the Inland water from the other class of water represents the Coastline.	
L4165	Ferry Crossing	The route used to carry or convey people or cargo back and forth over a waterbody in a boat.	
P0001	Nonvisible Linear Legal/Statistical Boundary	A legal/statistical boundary line that does not correspond to a shoreline or other visible feature on the ground.	
P0002	Perennial Shoreline	The more-or-less permanent boundary between land and water for a water feature that exists year-round.	
P0003	Intermittent Shoreline	The boundary between land and water (when water is present) for a water feature that does not exist year-round.	
P0004	Other non-visible bounding Edge (e.g., Census water boundary, boundary of	A bounding Edge that does not represent a legal/statistical boundary, and does not correspond to a shoreline or other visible feature on the ground. Many such Edges bound area landmarks, while many others separate water features from	

MTFCC	Feature Class	Feature Class Description	
	an areal feature)	each other (e.g., where a bay meets the ocean).	
R1011	Railroad Feature (Main, Spur, or Yard)	A line of fixed rails or tracks that carries mainstream railroad traffic. Such a rail line can be a main line or spur line, or part of a rail yard.	
R1051	Carline, Streetcar Track, Monorail, Other Mass Transit	Mass transit rail lines (including lines for rapid transit, monorails, streetcars, light rail, etc.) that are typically inaccessible to mainstream railroad traffic and whose tracks are not part of a road right-of-way.	
R1052	Cog Rail Line, Incline Rail Line, Tram	A special purpose rail line for climbing steep grades that is typically inaccessible to mainstream railroad traffic. Note that aerial tramways and streetcars (which may also be called "trams") are accounted for by other MTFCCs and do not belong in R1052.	
S1100	Primary Road	Primary roads are generally divided, limited-access highways within the interstate highway system or under state management, and are distinguished by the presence of interchanges. These highways are accessible by ramps and may include some toll highways.	
S1200	Secondary Road	Secondary roads are main arteries, usually in the U.S. Highway, State Highway or County Highway system. These roads have one or more lanes of traffic in each direction, may or may not be divided, and usually have at-grade intersections with many other roads and driveways. They often have both a local name and a route number.	
S1400	Local Neighborhood Road, Rural Road, City Street	Generally a paved non-arterial street, road, or byway that usually has a single lane of traffic in each direction. Roads in this feature class may be privately or publicly maintained. Scenic park roads would be included in this feature class, as would (depending on the region of the country) some unpaved roads.	
S1500	Vehicular Trail (4WD)	An unpaved dirt trail where a four-wheel drive vehicle is required. These vehicular trails are found almost exclusively in very rural areas. Minor, unpaved roads usable by ordinary cars and trucks belong in the S1400 category.	
S1630	Ramp	A road that allows controlled access from adjacent roads onto a limited access highway, often in the form of a cloverleaf interchange. These roads are unaddressable and do not carry a name in the MAF/TIGER System.	
S1640	Service Drive usually along a limited access highway	A road, usually paralleling a limited access highway, that provides access to structures along the highway. These roads can be named and may intersect with other roads.	
S1710	Walkway/Pedestrian Trail	A path that is used for walking, being either too narrow for or legally restricted from vehicular traffic.	
S1720	Stairway	A pedestrian passageway from one level to another by a series of steps.	
S1730	Alley	A service road that does not generally have associated addressed structures and is usually unnamed. It is located at the rear of buildings and properties and is used for deliveries.	
S1740	Private Road for service vehicles (logging, oil fields, ranches, etc.)	A road within private property that is privately maintained for service, extractive, or other purposes. These roads are often unnamed.	

MTFCC	Feature Class	Feature Class Description
S1750	Internal U.S. Census Bureau use	Internal U.S. Census Bureau use.
S1780	Parking Lot Road	The main travel route for vehicles through a paved parking area.
S1820	Bike Path or Trail	A path that is used for manual or small, motorized bicycles, being either too narrow for or legally restricted from vehicular traffic.
S1830	Bridle Path	A path that is used for horses, being either too narrow for or legally restricted from vehicular traffic.
S2000	Road Median	The unpaved area or barrier between the carriageways of a divided road.
Note: The information in this table was last updated in November 2017.		

# APPENDIX D. STANDARD STREET TYPE ABBREVIATIONS

Street Name Type	Standard Abbreviation
ALLEY	ALY
ANEX	ANX
ARCADE	ARC
AVENUE	AVE
BAYOU	BYU
BEACH	BCH
BEND	BND
BLUFF	BLF
BLUFFS	BLFS
ВОТТОМ	BTM
BOULEVARD	BLVD
BRANCH	BR
BRIDGE	BRG
BROOK	BRK
BROOKS	BRKS
BURG	BG
BURGS	BGS
BYPASS	BYP
CAMP	CP
CANYON	CYN
CAPE	CPE
CAUSEWAY	CSWY
CENTER	CTR
CENTERS	CTRS
	CIRS
CIRCLE	
CHEE	CIRS
CLIFF	CLF
CLIFFS	CLFS
CLUB	CLB
COMMON	CMN
COMMONS	CMNS
CORNER	COR
CORNERS	CORS
COURSE	CRSE
COURT	CT
COURTS	CTS
COVE	CV
COVES	CVS
CREEK	CRK
CRESCENT	CRES
CREST	CRST
CROSSING	XING
CROSSROAD	XRD
CROSSROADS	XRDS
CURVE	CURV
DALE	DL
DAM	DM
DIVIDE	DV
DRIVE	DR

Street Name Type	Standard Abbreviation
DRIVES	DRS
ESTATE	EST
ESTATES	ESTS
EXPRESSWAY	EXPY
EXTENSION	EXT
EXTENSIONS	EXTS
FALL	FALL
FALLS	FLS
FERRY	FRY
FIELD	FLD
FIELDS	FLDS
FLAT	FLT
FLATS	FLTS
FORD	FRD
FORDS	FRDS
FOREST	FRST
FORGE	FRG
FORGES	FRGS
FORGES	FRK
FORKS	FRKS
FORT	FT
FREEWAY	FWY
GARDEN	GDN
GARDENS	GDNS
GATEWAY	GTWY
GLEN	GLNC
GLENS	GLNS
GREEN	GRN
GREENS	GRNS
GROVE	GRV
GROVES	GRVS
HARBOR	HBR
HARBORS	HBRS
HAVEN	HVN
HEIGHTS	HTS
HIGHWAY	HWY
HILL	HL
HILLS	HLS
HOLLOW	HOLW
INLET	INLT
ISLAND	IS
ISLANDS	ISS
ISLE	ISLE
JUNCTION	JCT
JUNCTIONS	JCTS
KEY	KY
KEYS	KYS
KNOLL	KNL
KNOLLS	KNLS
LAKE	LK
LAKES	LKS
LAND	LAND

Stroot Name Type	Standard Abbroviation
Street Name Type LANDING	Standard Abbreviation LNDG
LANE	LNDG
LIGHT	LGT
LIGHTS	LGTS
LOCK	LF
LOCK	LCK
LOCKS	LCKS
LODGE	LDG
LOOP	LOOP
MALL	MALL
MANOR	MNR
MANORS	MNRS
MEADOW	MDW
MEADOWS	MDWS
MEWS	MEWS
MILL	ML
MILLS	MLS
MISSION	MSN
MOTORWAY	MTWY
MOUNT	MT
MOUNTAIN	MTN
MOUNTAINS	MTNS
NECK	NCK
ORCHARD	ORCH
OVAL	OVAL
OVERPASS	OPAS
PARK	PARK
PARKS	PARK
PARKWAY	PKWY
PARKWAYS	PKWY
PASS	PASS
PASSAGE	PSGE
PATH	PATH
PIKE	PIKE
PINE	PNE
PINES	PNES
PLACE	PL
PLAIN	PLN
PLAINS	PLNS
PLAZA	PLZ
POINT	PT
POINTS	PTS
PORT	PRT
PORTS	PRTS
PRAIRIE	PR
RADIAL	RADL
RAMP	RAMP
RANCH	RNCH
RAPID	RPD
RAPIDS	RPDS
REST	RST
RIDGE	RDG
INDGL	ווטט

Street Name Type	Standard Abbreviation
RIDGES	RDGS
RIVER	RIV
ROAD	RD
ROADS	RDS
ROUTE	RTE
ROW	ROW
RUE	RUE
RUN	RUN
SHOAL	SHL
SHOALS	SHLS
SHORE	SHR
SHORES	SHRS
SKYWAY	SKWY
SPRING	SPG
SPRINGS	SPGS
SPUR	SPUR
SPURS	SPUR
SQUARE	SQ
SQUARES	SQS
STATION	STA
STRAVENUE	STRA
STREAM	STRM
STREET	ST
STREETS	STS
SUMMIT	SMT
TERRACE	TER
THROUGHWAY	TRWY
TRACE	TRCE
TRACE	TRAK
TRAFFICWAY	TRFY
TRAIL	TRL
TRAILER	TRLR
TUNNEL TURNPIKE	TUNL
	TPKE
UNDERPASS	UPAS
UNION	UN
UNIONS	UNS
VALLEY	VLY
VALLEYS	VLYS
VIADUCT	VIA
VIEW	VW
VIEWS	VWS
VILLAGE	VLG
VILLAGES	VLGS
VILLE	VL
VISTA	VIS
WALK	WALK
WALKS	WALK
WALL	WALL
WAY	WAY
WAYS	WAYS
WELL	WL


Street Name Type	Standard Abbreviation
WELLS	WLS

### **APPENDIX E. GUPS TOOLS**

### E.1 Set Layer Symbology

GUPS loads a default layer symbology established for each Census Bureau geographic partnership program. You can change the default symbology to suit your preferences. To change the default symbology for a layer in GUPS, follow the instructions in **Table 50**.


**Table 50: Reset Layer Symbology** 




#### Step Action and Result

Step 3


In the left-hand pane, click on **Style**, then double-click the symbol you want to edit in the layers list. In this example, we will double-click on 'Roads, substr ("MTFCC, 1,1) = S1100' to select it.



The **Rule Properties** dialog box opens and the **Label** and **Filter** fields display the item chosen. The **Symbol** pane shows the current symbology (yellow line).




Step 4 Choose a new color from the Color drop-down menu, or select a different symbol for the layer altogether by double-clicking any symbol in the Symbols in Group field. Click OK. The new symbology will display in the Table of Contents and in Map View.





## **E.2** Change Label Display

You can change the default GUPS labeling display and also restore it to the original setting. To change the default labeling for a layer, follow the steps in **Table 51**.

**Table 51: Change Default Labeling** 








# **E.3** Restoring Default Label Display Settings

To restore the default labeling for a layer, follow the steps in Table 52.

**Table 52: Restoring Default Labeling** 

Step	Action and Result
Step 1	Right-click on the layer you changed in the <b>Table of Contents</b> . <i>The layer's drop-down menu opens</i> .
Step 2	In this example, we have selected the Edges layer. In the drop-down menu, click on the arrow to the right of 'GUPS Layer'. Four options appear: 'Load default style', 'Load all default style', 'Load BBSP Edges style', and 'Load Low profile Edges style'.



### E.4 Using the Table of Contents Toolbar to Manage Layers

Using the buttons on the toolbar located at the top of the Table of Contents, you can add and remove layers or groups, manage layer visibility, filter the legend by map content, expand or contract all sections of the Table of Contents list at once, and group layers.

The Table of Contents Layers toolbar contains the items shown below in Figure 20.

Table 53: Table of Contents Layers Toolbar Buttons describes the function of each of the buttons on the toolbar.



**Figure 20. Table of Contents Layers Toolbar** 

**Table 53: Table of Contents Layers Toolbar Buttons** 

Button	Name	Function / Description
đ	Add Group	Allows you to organize layers in the <b>Table of Contents</b> into groups.
<b>®</b>	Manage Layer Visibility	Allows you to preset views in the <b>Table of Contents</b> .
7	Filter Legend by Map Content	Removes from the <b>Table of Contents</b> display any layers that are not currently in the <b>Map View</b> extent. This feature ensures that the <b>Table of Contents</b> does not contain entries for items not currently in the map view.
E:	Expand All	Expands the <b>Table of Contents</b> menus (+) to display all layers under each group's menu.
E	Collapse All	Collapses the <b>Table of Contents</b> menus (-) to show only groups.
	Remove Layer/Group	Allows you to remove a layer or group from the <b>Table of Contents</b> .

## E.5 Preset Views in the Manage Layer Visibility Table of Contents

You can add preset views in the Table of Contents by clicking on the Manage Layer Visibility button on the Table of Contents toolbar. You can choose to display a layer with specific categorization and add this view to the Presets list.

To add a preset view click on the Manage Layer Visibility button and choose 'Add Preset...' from the drop-down menu.



Figure 21. Add Preset Layer

When the **Visibility Presets** pop-up appears, enter the name of the new preset and click **OK.** 



Figure 22. Visibility Presets Dialog Box



Note: By clicking on the Manage Layer Visibility button, you can view the list of all preset views that you have established and from which you can choose.



# Add a Layer

Clicking on the Add Vector Layer button on the Add Data toolbar allows you to add shapefile and geodatabase feature classes to your GUPS project. Instructions and accompanying graphics are included in Section 5.7.1: The Add Data Toolbar.



## Remove a Layer or Group

To remove a layer or group in the Table of Contents:

Left-click on the layer/group you want to remove, hold down the CTRL key, and click the Remove a Layer or Group button. The layer/group is removed.

# APPENDIX F. MAF/TIGER FEATURE CLASSIFICATION

**Table 54: MAF/TIGER Feature Classification** 

MTFCC	FEATURE NAME
S1100	Interstate Highway or Primary Road with limited access
S1200	Primary Road without limited access, US Highway, State Highway, or County Highway, Secondary and connecting roads
S1400	Local Neighborhood Road, Rural Road, City Street
S1500	Vehicular Trail (4WD)
S1630	Ramp
S1640	Service Drive usually along a limited access highway
S1710	Walkway/Pedestrian Trail
S1720	Stairway
S1730	Alley
S1740	Private Road for service vehicles (logging, oil fields, ranches, etc.)
S1750	Private Driveway
H3010	Stream/River
H3013	Braided Stream
H3020	Canal, Ditch or Aqueduct
R1011	Railroad Feature (Main, Spur, or Yard)
R1051	Carline, Streetcar Track, Monorail, Other Mass Transit Rail
R1052	Cog Rail Line, Incline Rail Line, Tram
P0001	Nonvisible Legal/Statistical Boundary
L4010	Pipeline
L4020	Power Transmission Line
L4110	Fence Line
L4121	Ridge Line
L4031	Aerial Tramway/Ski Lift
K2451	Airport or Airfield
L4140	Property/Parcel Line
L4165	Ferry Crossing



## APPENDIX G. SHAPEFILE NAMES

### **State Shapefile Names**

**PVS\_18\_v2\_<layername>\_<SS>.shp**, where <SS> is the number corresponding to the state, for example, "24" and <layername> is the abbreviation for the shapefile layer, describe in detail below.

**Table 55: State Shapefiles Names** 

Shapefile Layer	<layername></layername>
American Indian Areas (AIA) – Legal	aial
2010 American Indian Areas (AIA) – Legal	aial2010
American Indian Areas (AIA) – Statistical	aias
American Indian Tribal Subdivisions (AITS) - Legal	aitsl
American Indian Tribal Subdivisions (AITS) - Statistical	aitss
Block Area Group	bag
Metropolitan Statistical Area/Metropolitan Statistical Area	cbsa
Congressional Districts	cd
Census Designated Place	cdp
Counties and Equivalent Areas	county
2010 Counties and Equivalent Areas	county2010
Elementary School Districts	elsd
County Subdivisions - Legal	mcd
New England City and Town Areas	necta
Incorporated Places	place
2010 Public Use Microdata Areas	puma2010
Secondary School Districts	scsd
State Legislative Districts Lower	sldl
State Legislative District Upper Chambers	sldu
State	state
Tribal Block Groups	tbg
Tribal Census Tracts	tct
2010 Census Tracts	tracts2010
Urban Area	uac
Unified School District State-Based	unsd

## **County Shapefile Names**

**PVS\_18\_v2\_<layername>\_<SSCCC>.shp,** where <SSCCC> is the number corresponding to the state and county, for example, "24001" and <layername> is the abbreviation for the shapefile layer, describe in detail below.

**Table 56: County Shapefiles Names** 

Shapefile Layer	<layername></layername>
American Indian Areas (AIA) – Legal	aial
American Indian Areas (AIA) – Statistical	aias
American Indian Tribal Subdivisions (AITS) - Legal	aitsl
American Indian Tribal Subdivisions (AITS) - Statistical	aitss
Alaska Native Regional Corporations (ANRC)	anrc
Area Landmark	arealm
Block Area Groups	bag
Block Groups	bg
Metropolitan Statistical Area/Metropolitan Statistical Area	cbsa
Census County Division	ccd
Congressional Districts	cd
Census Designated Place	cdp
Consolidated Cities	concity
Counties and Equivalent Areas	county
Census Tracts - Current	curtracts
All Lines	edges
Elementary School Districts	elsd
Hawaiian Home Lands (HHL)	hhl
County Subdivisions - Legal	mcd
New England City and Town Areas	necta
Offsets	offset
Incorporated Places	place
Point Landmarks	pointlm
2010 Public Use Microdata Areas	puma2010
Secondary School Districts	scsd
State Legislative Districts Lower	sldl
State Legislative Districts Upper	sldu
Subbarrios	submcd

Shapefile Layer	<layername></layername>
Census Blocks - Current	tabblock
2010 Census Blocks	tabblock2010
2010 Traffic Analysis Delineation	tad2010
2010 Traffic Analysis Zones	taz2010
Tribal Block Groups	tbg
Tribal Census Tracts	tct
2010 Census Tracts	tracts2010
Census Urban Areas	uac
Urban Growth Area	uga
Hydrography - Area	water
Unified School Districts	unsd
Relationship Tables	
Address Ranges	addr
Topological Faces (2-cells with all geocodes)	faces
Topological Faces - Area Landmark Relationship	areafaces
Topological Faces - Area Hydrography Relationship	hydrofaces
Linear Feature Names - Fielded	allnames

# **APPENDIX H. SHAPEFILE LAYOUTS**

Table 57: Edges Shapefile (PVS\_18\_v2\_edges)

ATTRIBUTE FIELD	LENGT H	ТҮРЕ	DESCRIPTION
STATEFP	2	String	FIPS state code
COUNTYFP	3	String	FIPS county code
TLID	10	Double	Permanent edge ID
TFIDL	10	Double	Permanent face ID (left)
TFIDR	10	Double	Permanent face ID (right)
MTFCC	5	String	MAF/TIGER Feature Class Code
FIDELITY	1	String	Indication to a respondent when their entity boundary has changed through spatial enhancement
FULLNAME	40	String	Decoded feature name with abbreviated qualifier, direction, and feature type
SMID	22	String	Spatial Theta ID
SMIDTYPE	1	String	SMIDTYPE code
BBSPFLG	1	String	Redistricting data project participant's submitted request of an EDGE for selection as a block boundary
CBBFLG	1	String	Indicates the status of an EDGE for a selection as a block boundary
BBSP_2020	1	String	New BBSP flag
CHNG_TYPE	4	String	Type of linear feature update
JUSTIFY	150	String	Justification of change
LTOADD	10	String	Left To address
RTOADD	10	String	Right To address
LFROMADD	10	String	Left From address
RFROMADD	10	String	Right From address
ZIPL	5	String	Left zip code

ZIPR	5	String	Right zip code
EXTTYP	1	Char	Extension type
MTUPDATE	10	Date	Date of last update to the edge

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
OID	8	STRING	Object ID
TLID	22	INTEGER	TIGER Line ID
STATEFP	2	STRING	FIPS State Code
COUNTYFP	3	STRING	FIPS County Code
FROMHN	12	STRING	From House Number
TOHN	12	STRING	To House Number
SIDE	1	STRING	Side Indicator Flag
ZIP	5	STRING	5-digit ZIP Code
PLUS4	4	STRING	ZIP+4 Code
LFROMADD	10	STRING	Left From Address
LTOADD	10	STRING	Left To Address
RFROMADD	10	STRING	Right From Address
RTOADD	10	STRING	Right To Address
ZIPL	5	STRING	Left 5-digit ZIP Code
ZIPR	5	STRING	Right 5-digit ZIP Code
ZIP4L	4	STRING	Left ZIP+4 Code
ZIP4R	4	STRING	Right ZIP+4 Code

Table 58: Address Ranges Attribute File (PVS\_18\_v2\_addr)

Table 59: Census Block Shapefile (PVS\_18\_v2\_tabblock2010)

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
BLKSZIND	1	String	Block Size Indicator
BLOCK	4	String	Block Number
BLOCKCE	4	String	Tabulation Block Number
BLOCKID	15	String	FIPS State Code, FIPS County Code, Census Tract Code, Block Number
COUNTYFP	3	String	Census County FIPS code
COUNTYFP10	3	String	FIPS County Code
FID	10	Integer	Permanent Face ID
NCELIGBLE	1	String	New Construction Program eligible
PARTFLG	1	String	Part Flag Indicator
Shape	7	String	Type of shape
STATEFP	2	String	Census state FIPS code
STATEFP10	2	String	FIPS State Code
SUFFIX1CE	2	String	Census Block Suffix 1
SUFFIX2CE	2	String	Census Block Suffix 2
TRACTCE10	6	String	Census tract code

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
CHNG_TYPE	2	String	Type of area update
COUNTYFP	3	String	FIPS County Code
EFF_DATE	8	String	Effective Date or Vintage
FID	10	Integer	Permanent Face ID
JUSTIFY	150	Char	Justification
NAME	100	String	Name
NEW_CODE	2	String	New Congressional District Code
RELATE	120	String	Relationship Description
Shape	7	String	Type of shape
STATEFP	2	String	FIPS State Code
TRACTCE	6	String	Census Tract Code
TRACTID	11	String	FIPS State Code, FIPS County Code, Census Tract Code
TRACTLABEL	7	String	Tract number used for LUCA geocoding
TRACTTYP	1	String	Tract Characteristic Flag
VINTAGE	2	String	Vintage updated with returned data

Table 60: Census Tract Shapefile (PVS\_18\_v2\_curtracts)

Table 61: American Indian Areas Shapefile (PVS\_18\_v2\_aial)

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
AIANNHCE	4	String	Census AIANNH Code
AIANNHFSR	1	String	Flag Indicating Level of Recognition of an AIA
AIANNHNS	8	String	ANSI numeric identifier for AIA areas
AREA	10	Double	Acreage of Area Update
AUTHTYPE	1	String	Authorization Type (O – Ordinance, R – Resolution, L – Local Law, S – State Level Action, X – Other)
CHNG_TYPE	2	String	Type of Area Update
CLASSFP	2	String	FIPS 55 Class Code Describing an Entity
COMPTYP	1	String	Indicates if Reservation, Trust Land, or both are Present
COUNTYFP	3	String	FIPS County Code
DOCU	120	String	Supporting Documentation
EFF_DATE	8	Date	Effective Date
FID	10	Integer	Permanent Face ID
FORM_ID	4	String	(MTPS and Web BAS Only)
FUNCSTAT	1	String	Functional Status
JUSTIFY	150	Char	Justification
LSAD	2	String	Legal / Statistical Area Description
NAME	100	String	AIA name
NAMELSAD	100	String	Name with Translated LSAD
PARTFLG	1	String	Part Flag Indicator
RELATE	120	String	Relationship description
SHAPE	7	String	Type of shape
STATEFP	2	String	FIPS State Code
VINTAGE	2	String	Vintage of the Data

Table 62: County and Equivalent Areas Shapefile (PVS\_18\_v2\_county)

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
STATEFP	2	String	FIPS state code
COUNTYFP	3	String	FIPS county code
COUNTYNS	8	String	ANSI feature code for the county or equivalent feature
NAMELSAD	100	String	Name with translated LSAD code
LSAD	2	String	Legal/Statistical Area Description code
FUNCSTAT	1	String	Functional status
CLASSFP	2	String	FIPS 55 class code describing an entity
CHNG_TYPE	2	String	Type of area update
EFF_DATE	8	Date	Effective date or vintage
AUTHTYPE	1	String	Authorization type (O – Ordinance, R – Resolution, L – Local Law, S – State Level Action, X – Other)
DOCU	120	String	Supporting documentation
FORM_ID	4	String	Record ID (GUPS only)
AREA	10	Double	Area of update
RELATE	120	String	Relationship description
JUSTIFY	150	String	Justification of change
NAME	100	String	Entity name
VINTAGE	2	String	Vintage of the data

Table 63: County Subdivisions Shapefile (PVS\_18\_v2\_mcd)

ATTRIBUTE FIELD	LENGTH	TYPE	DESCRIPTION
STATEFP	2	String	FIPS state code
COUNTYFP	3	String	FIPS county code
COUSUBFP	5	String	FIPS 55 county subdivision code
NAMELSAD	100	String	Name with translated LSAD
COUSUBNS	8	String	ANSI feature code for the county subdivision
LSAD	2	String	Legal/Statistical Area Description
FUNCSTAT	1	String	Functional status
CLASSFP	2	String	FIPS 55 class code describing an entity
CHNG_TYPE	2	String	Type of area update
EFF_DATE	8	Date	Effective date or vintage
AUTHTYPE	1	String	Authorization type (O – Ordinance, R – Resolution, L – Local Law, S – State Level Action, X – Other)
DOCU	120	String	Supporting documentation
FORM_ID	4	String	Record ID (GUPS only)
AREA	10	Double	Area of update
RELATE	120	String	Relationship description
JUSTIFY	150	String	Justification of change
NAME	100	String	Entity name
VINTAGE	2	String	Vintage of the data

Table 64: Incorporated Place Shapefile (PVS\_18\_v2\_place)

ATTRIBUTE FIELD	LENGT H	TYPE	DESCRIPTION
STATEFP	2	String	FIPS state code
COUNTYFP	3	String	FIPS county code
PLACEFP	5	String	FIPS 55 place code
NAMELSAD	100	String	Name with translated LSAD
PLACENS	8	String	ANSI feature code for the place
LSAD	2	String	Legal / Statistical Area Description
FUNCSTAT	1	String	Functional status
CLASSFP	2	String	FIPS 55 class code describing and entity
PARTFLG	1	String	Indicates if only part of a feature is represented
CHNG_TYPE	2	String	Type of area update
EFF_DATE	8	Date	Effective date or vintage
AUTHTYPE	1	String	Authorization type (O – Ordinance, R – Resolution, L – Local Law, S – State Level Action, X – Other)
DOCU	120	String	Supporting documentation
FORM_ID	4	String	Record ID (GUPS only)
AREA	10	Double	Area of update
RELATE	120	String	Relationship description
JUSTIFY	150	String	Justification of change
NAME	100	String	Entity name
VINTAGE	2	String	Vintage of the data